

16-21-13W

KANSAS WELL LOG BUREAU---KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY WESTGATE GREENLAND OIL CO.

SEC. 16- T. 21 R. 13W

FARM Grow

NO. 8

LOC. SW NW SE

TOTAL DEPTH 3675'

COMM. 2-4-51


COMP. 2-26-51

SHOT OR TREATED

CONTRACTOR Jackson Drilling

ISSUED 5-5-51

COUNTY Stafford
KANSAS



CASING

10-3/4" 269' cem. w/200 sxs cem. & 2 sxs c.c.
7" 3661' cem. w/75 sxs

ELEVATION 1896

PRODUCTION Pot. 375 bbls.

FIGURES INDICATE BOTTOM OF FORMATIONS

loose sand	60
clay & sand	70
sand	80
pyrite & sand	90
sand & pyrite	103
shale & shells	269
redbed & shells	750
sand & lime	760
anhydrite	780
shale & shells	1510
shale & lime	1675
lime	1830
lime & shale	1890
lime	2105
lime & shale	2140
shale & shells	2235
shale & lime	2270
lime	2295
lime & shale	2850
lime	3155
lime & shale	3227
lime	3255
lime & shale	3295
shale	3328
lime	3483
lime & shale	3505
lime	3583
viola chert	3621
shale	3658
arbuckle	3675
Total Depth	

Drill stem test 3661-3667 ' Open
1 1/4 hrs-recovered 75' of heavy
oil & gas cut mud.
Drill stem test 3669-3675 'Open
1 1/4 hrs-recovered 810 ft. free
oil, 1200' gas in pipe.

All measurements from top of
derrick floor.

Tops:	
Anhydrite	760
Heebner	3205
Brown Lime	3325
Lansing	3340
Viola	3580
Simpson	3618
buckle	3656