

18-21-13W

Company - PETROLEUM, INC.

Farm - Brown "A"

No. 3

SEC. 18 T. 21 R. 13W

SW NW SW

Total Depth. 3686

Comm. 7-2-50

Comp.

7-13-50 ✓

County.


Stafford

KANSAS

Shot or Treated.

Contractor. Carvey Oil Co.

Issued. 7-29-50



1921RB13W

Elevation. 1919 D.F.

CASING:

8 5/8" 254.23'

Production. Dry

Figures Indicate Bottom of Formations.

surface soil	35
sand	125
shale	200
shale, shells	245
sand	310
red bed	804
anhyd.	825
shale, shells	1045
lime shale	1570
lime	1755
lime shale	1865
shale, shells	2095
lime, shale	2210
shale, shells	2325
lime, shale	2665
shale, shells	2730
lime, shale	2930
lime	3085
lime, shale	3145
lime	3195
lime, shale	3280
lime	3506
shale	3581
conglomerate	3593
chert	3606
shale	3640
lime	3686
Total depth	

Tops:

Anhydrite	814
Heebner	3224
Toronto	3245
Base Oread	3263
Brown lime	3346
Lansing	3358
Base Kansas City	3558
Viola	3594
Simpson shale	3622
Simpson sand	3646
Arbuckle	3680

DST #1, 3582-3606, rec. 3' mud.

DST #2, 3647-70, rec. 5' mud.

DST #3, 3682-3686, rec. 300' water.