

18-21-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- STANOLIND OIL & GAS CO.
Farm- Alvin Fischer No. 1

SEC. 18 T. 21 R. 13W
CS/2 SW SE
330' N. of SL & 1980' W. of EL

Total Depth. 3692
Comm. 9-20-51 Comp. 10-14-51
Shot or Treated.
Contractor.
Issued. 3-29-52

County Stafford
KANSAS



CASING:
10 3/4" 817' cem. w/450 sx
7" 3685' cem. w/150 sx

Elevation. 1917 RDB
1914 (cont)
Production. 494 BO

Figures Indicate Bottom of Formations.

- clay 30
- sand 105
- sand, clay, shale 455
- sand, shale 500
- red bed 670
- shale, shells 810
- anhydrite 830
- red bed, shale 1115
- shale, shells 1750
- shale, lime, shale 1890
- lime, shale 1975
- lime, sand, strks 2025
- li, shale 2735
- shale 2915
- lime, shale 2985
- lime 3095
- lime, shale 3145
- lime 3235
- lime, shale 3355
- lime, shale 3373
- lime, odor of oil in samples 3378
- lime, shale 3480
- show of heavy blk oil 3498
- lime, shale, so in lime 3516
- lime, shale, show of heavy oil 3554
- lime, shale 3684
- shale 3689
- dolo. lime, oil shows 3692
- Total Depth

Tops:
Lansing 3355-3684
Arbuckle 3684-3692

Total Depth:
By Schlumberger 3692
By Rotary Drill 3692