

19-21-13W

KANSAS WELL LOG BUREAU --- KANSAS GEOLOGICAL SOCIETY
508 EAST MURDOCK - WICHITA, KANSAS

COMPANY PETROLEUM, INC.


SEC. 19 T. 21 R. 13W

FARM Hufford "B" NO. 1

LOC. SE NE NE

TOTAL DEPTH 3790
 COMM. 10-20-50 COMP. 10-29-50
 SHOT OR TREATED
 CONTRACTOR Garvey Oil
 ISSUED 11-18-50

COUNTY Stafford



CASING

8 5/8" 217'

ELEVATION 1911 DF

PRODUCTION

1913 R.D. No.
dry

FIGURES INDICATE BOTTOM OF FORMATIONS

clay & sand	160
shale, shells	210
shale	217
shale, shells	1207
salt, shale	1595
shale, shells	1830
lime, shale	2020
br. lime	2170
shale, shells	2315
shale, lime	2775?
shale, shells	2925
shale, lime	3073
lime sandy	3175
lime	3217
lime, shale	3301
lime	3400
conglomerate	3638
Viola	3695
shale	3700
lime	3755
lime	3790
Total Depth	

Tops:

Heebner	3246
Br. Lime	3368
Lansing	3381
Conglomerate	3618
Viola	3640
Simpson	3695
Arbuckle	3747

DST # 1 3748-55, open 30 mins.,
 closed 15 mins., recovered 5'
 drilling fluid.