

19-21-13W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Petroleum, Inc.
Company- GARVEY OIL CO.
Farm- Hufford "B" No. 2

SEC. 19 T. 21 R. 13W
NW NW NE

Total Depth. 3741
Comm. 12-26-51 Comp. 1-7-52
Shot or Treated.
Contractor. Rocket Drlg.
Issued. 3-8-52

County Stafford
KANSAS



CASING:
8 5/8" 367' cem. w/378 sx.
5 1/2" 3740' cem. w/75 sx.

Elevation. 1914
1916 (rod)
Production. 34 bbls. / 40% wtr.

Figures Indicate Bottom of Formations.

| | |
|----------------------|------|
| sand | 332 |
| shale | 367 |
| shale & red sand | 811 |
| anhyd. | 835 |
| shale, shells & salt | 1320 |
| shale & shells | 1645 |
| shale & lime | 1810 |
| lime | 1835 |
| sand | 1852 |
| shale & lime | 2020 |
| shale sdy | 2037 |
| shale & lime | 2095 |
| lime | 2210 |
| lime & shale | 2355 |
| shale & lime | 2510 |
| shale & shells | 2735 |
| lime & shale | 2890 |
| lime | 3265 |
| shale | 3342 |
| shale & lime | 3385 |
| lime | 3581 |
| lime & chert | 3638 |
| chert & shale | 3680 |
| shale & Arb. lime | 3695 |
| Arb. lime | 3741 |
| Total Depth | |
| Tops: Scout | |
| Reebner | 3235 |
| Brown lime | 3353 |
| Lansing | 3365 |
| Viola | 3608 |
| Simpson | 3640 |
| Arb. | 3691 |