

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,


Wichita, Kansas

19-21-13W

Company- STANOLIND OIL & GAS CO.
Farm- K. Pundsack "A" No. 2

SEC. 19 T. 21 R. 13W
CN/2 NW SE
330' S. of NL & 660' E. of
WL of SE $\frac{1}{4}$
County Stafford
KANSAS

Total Depth. 3792
Comm. 11-6-51 Comp. 11-14-51
Shot or Treated.
Contractor.
Issued. 2-23-52



CASING:

8 5/8" 814' cem. w/500 sx
5 1/2" 3792' cem. w/175 sx

Elevation. 1917 RDB

Production. 424 BO

Figures Indicate Bottom of Formations.

surface sand	70
shale, shells	145
sand	175
shale, shells	200
shale, red bed	600
red bed, sand, gravel	807
anhydrite	1190
shale, shells	1735
shale, lime	2490
shale	2670
shale, lime	2800
lime	3363
lime w/oil stains	3451
lime, bleeding oil stains	3496
lime, sh. strks, s. oil & gas	3556
lime, shale	3577
lime	3626
lime, chert	3710
lime, shale	3717
lime, shale strks oil show	3731
lime, shale, sulphur water	3792 RTD
Total Depth	

Tops:

Lansing 3363-3609
Arbuckle 3717-3792

Ran Schlumberger logs to TD
Plugged back w/cement to 3750 $\frac{1}{2}$ '
Completed as an Arbuckle producer 12-20-51
from perf: 3718-3720