

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
508 E. Murdock,
Wichita, Kansas

20-21-13W

Company - PETRO., INC.
Farm - Koopman

No. 1

SEC. 20 T. 21 R. 13W
NE NW NE

Total Depth. 3679

Comm. 11-30-49


Comp. 12-14-49

Shot or Treated.

Contractor. Stag Drilg. Co.

Issued. 5-13-50

County. Stafford
KANSAS



Elevation. 1902 ft.

Production. Pot. 311 bbls.

CASING:

8 5/8" surface 303'
5 1/2" 3675'

ALL MEASUREMENTS FROM TOP OF ROTARY BUSHING.

Figures Indicate Bottom of Formations.

SURFACE gravel	35
lime sdy & p.t. iron	55
sand strks. p.t. iron	118
shale	150
shale, shells	220
sand, shale	301
shells	303
shale, shells, strks red	
rock	410
red bed	795
anhyd.	810
shale, shells	1570
lime, shale	1710
lime brkn	1790
lime	1933
lime, shale	1957
lime	1975
lime sdy	2060
shale, lime	2715
lime	3170
lime, sale	3330
lime	3590
Viola, chert	3622
Simpson sand	3673
lime R.T.D. ?	3675
Time	3679
Total Depth	

Tops:

Anhyd.	795
Heebner	3216
Tornanto	3233
Brown lime	3335
Lansing	3344
Viola	3590
Simpson	3619
Arbuckle	3673

D.S.T. 3469-78

op. 1 hr. rec. 60' oil cut mud.