

20-21-13W


WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
508 E. Murdock Wichita, Kansas

Company - PETROLEUM, INC.
Farm - Koopman No. 2
Koopman

SEC. 20 T. 21 R. 13W
SE NW NE

Total Depth. 3651
Comm. 1-14-50 Comp. 1-26-50
Shot or Treated.
Contractor. Drillers, Inc.
Issued. 5-13-50

County. Stafford
KANSAS



Elevation. 1904 ft

Production. Pot. 398 B0

CASING:

8 5/8" - 219-67'
5 1/2" - 3682'

Figures Indicate Bottom of Formations.

sand & shale	65
iron	95
shale & shells	140
shale & lime	206
shale & shells	250
sand	325
redbed	605
anhydrite	820
shale & shells	1160
lime & shale	1655
lime	1920
lime & shale	2145
shale & shells	2495
shale & lime	2655
lime	3100
shale	3231
shale & lime	3292
lime	3385
shale & lime	3581
conglomerate	3592
viola	3608
shale	3632
lime, Rotary TD	3678
lime	3681
Total depth	

TOPS:

Anhydrite	780
Heebner	3216
Toronto	3235
B. O.	3250
Brown lime	3336
Lansing	3347
BKC	3550
P.B.C.	3587
Viola	3592
Simpson	3626
Arbuckle	3675