

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY

412 Union National Bk. Bldg., Wichita, Kansas


22-21-13W

Company - PHILLIPS PETRO.CO.
 Farm - Krone No. 2.

SEC. 22 T. 21 R. 13 W
 CNW SW
 660'f N & W Lines SW $\frac{1}{4}$

Total Depth. 3751'
 Comm. 12-17-43 Comp. 2-28-44
 Shot or Treated.
 Contractor.
 Issued. 3-25-44

County. Stafford
 KANSAS



CASING:
 8 5/8" 376' Cem.
 5 1/2" 3678' Cem.

Elevation. _____

Production. Dry

Figures Indicate Bottom of Formations.

surface sand	40
sand rock	302
shale red bed, shells	390
red rock & shale	1000
red rock, shale, salt	1553
lime & shale	1718
sand & lime	1841
lime & shale	2173
shale, lime shells	2288
shale	2370
shale, lime strks	2455
shale & lime	2880
shale, lime strks	2993
lime	3083
lime & shale	3155
lime & shale strks	3249
lime & shale	3334
lime	3395
lime, shale strks	3520
lime	3575
lime & shale	3597
cherty congl.	3620
cherty congl. & lime	3667
lime	3751
Total Depth.	

Tops: Lansing K.C.	3345
Conglomerate	3595
Simpson	3624
Arbuckle	3676 $\frac{1}{2}$