

23-21-13W


WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- D.R. LAUCK OIL CO., INC.  
Farm- Hall No. 2

SEC. 23 T. 21 R-13W  
NW SW SW

Total Depth. 3695'  
Comm. 7-5-57 Comp. 7-17-57  
Shot or Treated.  
Contractor.  
Issued. 11-30-57

County Stafford  
KANSAS



Elevation. 1870' DF

Production. Dry

CASING:

10 3/4" 253' w/200 sx cem.  
5 1/2" 3669' w/100 sx cem.

Figures indicate Bottom of Formations

sand-clay	120
shale-shells	280
red bed	700
shale-shells	738
salt-shale	1565
lime-shale	1725
lime	1985
lime-shale	3005
lime	3195
Douglas	3306
Brown lime	3315
Lansing	3320
lime	3530
lime-chert	3611
Simpson	3651
shale-lime	3672
Arbuckle lime	3682 RTD
Arbuckle lime	3695
Total Depth	

TOPS:

Heebner	3177
Brown lime	3305
Lansing Kansas City	3321
B/Kansas City	3541
Conglomerate	3572
Viola	3581
Simpson	3610
Arbuckle	3667

DST #1--(M-D) 3323-3355 open  
1 hr., fair steady blow 1 hr;  
rec. 550' salt wtr; IFP 85#;  
FFP 295#, BHP 770#, 20 min.

DST #2--(M-D) 3360-3400 open  
1 hr; fair steady blow 1 hr;  
rec. 585' salt wtr; IFP 110#;  
FFP 370#; BHP 1115#, 20 min.

DST #3--(M-D) 3667-3670 tool  
plugged- no test.

DST #4-- (M-D) 3668-3672 Packer failure,  
no test.

DST #5-- 3671-3677 open 30  
min; rec. 55' rotary mud- BHP 380#  
in 20 min.

DST #6--(M-D) 3676-3682 RTD open  
30 min. weak blow 8 min. rec. 25'  
mud; flushed tool; BHP 32#, 20  
min.