

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

25-21-13W

Company- NADEL & GUSSMAN

Farm- Alpers

No. 2

SEC. 25 T. 21 R. 13W
SE SW NE

Total Depth. 3707

Comm. 10-31-51

Comp. 11-27-51

County Stafford
KANSAS

Shot or Treated.

Contractor.

Issued. 2-23-52

CASING:

8 5/8" 293' cem. w/225 sx


5 1/2" 3707' cem. w/125 sx

Elevation. 1872

1875 (and)

Production. 35 BO

Figures Indicate Bottom of Formations.



red bed, shells	610
red bed	696
anhydrite	745
red bed, shale, shells	770
shale & shells	1164
lime	1490
lime & shale	1575
lime broken	1695
lime	1750
lime, shale	1805
lime	1850
cherty lime & shale	1857
shale	1866
shale & shells	2010
lime & shale	2220
lime	3530
lime & shale	3577
cherty lime broken & shale	3608
cherty lime & shale	3636
shale & sand	3657
arbuckle	3707
Total Depth	

Tops:

Heebner Shale	3172
Brown Lime	3302
Lansing-K.C.	3317
Viola	3577
Simpson Shale	3651
Arbuckle	3657

Perf. 35 holes 3657-3665

500 Acid

Swabbed 5 1/2 BOPH