

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY

508 East Murdock,

Wichita, Kansas

29-21-13W

Company- CITIES SERVICE OIL CO.
Farm-Essmiller "B" No. 7

SEC. 29 T. 21 R. 13W
SE SW NW

1650' W & 330' N of Cent.

Total Depth. 3716

Comm. 9-3-52

Comp. 9-21-52


Shot or Treated. Acid: 380 gals(9-23) & 500 gals@ 3696

Contractor. Holm Drilling Co.

Issued. 1-24-53

County Stafford

KANSAS



Elevation. 1911

Production. Pot. 288 BO, 30 BW
24 hrs.

CASING:

8 5/8 361' w/ 250 sx cement
5 1/2 3712' w/ 150 sx cement

Figures Indicate Bottom of Formations.

clay & sand	97
iron & sand	121
sand	134
shale	362
shale & red bed	700
shale & shells	795
anhydrite	820
shale	1070
shale & shells	1435
shale	1600
lime & shale	1675
lime	1745
lime & shale	3065
lime	3224
lime & shale	3279
lime	3647
chert	3655
lime	3716
RTD 3716 - SLM 3714	
dolomite	3716
Total Depth	

TOPS: Corr.

Brown lime	3356
Lansing	3368
Viola	3623
Simpson	3642
Arbuckle	3711
Penetration	5

123' oil in 15 1/2 hrs.

9-23-52 Az. 500 gals. 380 gals. into form.
in 15 hrs. at 1200#.

Cleaned out 1 1/2' to 3716.

9-25-52 Set packer at 3696 & az. 500 gals.