

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY

503 East Murdock,

Wichita, Kansas

36-21-13W

Company- ANSCHUTZ DRILLING CO.
Farm-Fischer Estate No. 2

SEC. 36 T. 21 R. 13W
NE SW SW

Total Depth. 3710

Comm. 4-10-53

Comp. 4-20-53


Shot or Treated.

Contractor. Anschutz Drilling Co.

Issued. 7-25-53

County Stafford

KANSAS



Elevation. 1880 RB

Production. Dry

CASING:

8 5/8 set at 253' w/ 225 sx cement
5 1/2 set at 3709' w/ 150 sx cement

Figures indicate Bottom of Formations.

sand	235
red rock	252
red bed & shale	630
red rock	700
anhydrite	730
shale & shells	1500
lime	1550
shale, lime & sand	1640
sandy lime	1930
shale & lime	2355
shale & shells	2755
shale & lime	2900
lime	3010
lime & shale	3115
lime	3175
lime & shale	3310
lime	3612
chert, shale & sand	3660
lime	3710
Total Depth	

TOPS:

Anhydrite	700
Heebner	3185
Toronto	3204
Brown lime	3311
Lansing KC	3329
Base KC	
Conglomerate	3587
Simpson	3640
Arbuckle	3684

DST #1: 3348-99, open 1 hr. rec. 95'
muddy water, SI 30 min. BHP 1040#

DC 3076. Perf. 45/ 3685-93 VSS 1000 A
Swbd could not recover load. Perf.
36/ 3674-79 bailed 1 1/2 gal oil, 8 gal
water. Swbd 1 3/4 to 3 BFPH, wtr.
increased-oil decreased