

December, 1941.

Bodine #1 Willcutt,
C EL NE SE, 4~~2~~-21S-13W,
Elevation 1884'.
Rotary samples.

Pennsylvanian conglomerate 3505-3535'
3505-3510 Lime with rare chert and sand.
3510-3520 Sandy lime and some consolidated fine sand con-
taining chert fragments. Oilstained. Porosity
relatively poor.
3520-3535 Shales, vari-colored, and rare sandy lime.

Decorah 3535-3549'
3535-3549 Shales, red and green.

Arbuckle Top 3549'. Penetration 16' Sub-sea minus 1665'
3549-3565 Dolomite, medium to coarse at top; brown to
white medium below. Upper Miller.