

## SANDAGO

Form 113 -D

State Kansas County Stafford (T)Sec. 13 Twp. 21 Rng. 12w Elev. 1816Company Phillips Pet. Co.Well No. 2 Name EveleighLocation SW NE NE

Feet from lines: N. S. E. W.

Spud 10-10-47 Completed 12-17-47T. D. 3515 Casing

Comp. Perf.

Pay

I. P. TEMP. BRAND.

Choke T. P. C. P.

G. O. R. Grvty.

COMPLETION

DATE	REMARKS
12-17-47	Heeb. 3038, Brn. ln. 3160, Lans. 3180, Viola 3417, Simp. 3443, Arb. 3489, PSFO 3258-76, DST 3418-41, open 40 min., blew 5 min.,

DATE	REMARKS
	rec. 17' mud, TD 3495, FSFO
	5" 3495, DP DD 3511, 500 A,
	no help, DD 3515, FU 1675'
	wtr. + 425' oil,
	Swb/7 BO + 81 BW/10,
	FU 1700' fluid/7½ hrs.
	PB 3449, 52 § 3400-13 NS,
	56 § 3370-84, 56 § 3351-65,
	NS, 1500 A, B/123 GW + SO/12
	LWplug 3346, 44 § 3330-41,
	500 A, Swb/84 BW/19,
	drove plug to btm.
	LWplug 3300, 60 § 3270-85 NS,
	20 § 3258-63, 1 gal. muddy wtr.
	20 § 3250-55, NS, 1500 A,
	B/198 GW + scum oil/13
	drove plug 3443, set plug
	3246, 152 § 3189-3236, 1500A
	tst. 150.75 GW + scum oil/21
	drove plug to 3443 PBTD, SD
	TEMP. ABAND (may use for
	SWIM)
	Schlum tops -
	Heeb. 3040, Brn. lm. 3164, Lans.
	3184, Viola 3421, Simp. 3437,
	Arb. 3490, TD 3496.
	622689