

33-21-13W

WELL LOG BUREAU KANSAS GEOLOGICAL SOCIETY
412 Union National Bk Bldg. Wichita, Kansas

Company PHIL-HAN OIL COMPANY
Farm Hufford No. 1

SEC. 33 T. 21 R. 13W
SW SW NW

Total Depth. 3770'

Comm. 3-17-48

Comp. 4-1-48


Shot or treated.

Contractor.

Issued. 5-15-58

County. Stafford

KANSAS



Elevation. 1943.2nd.

Production. Pot. 368 Bbls.

CASING:
8-5/8" 305' Cem. W/300 Sx.
5" 3756' Cem. W/100 Sx.

Figures Indicate Bottom of Formations.

soil & sand	130
sand	250
shale & shells	300
sand & red rock	790
anhydrite	810
shale & shells	1090
shale & salt	1420
shale & shells	1560
lime & shale	1790
brkn lime	1865
lime	1915
lime & shale	2060
lime	2105
lime & shale	2715
lime	2785
lime & shale	2860
lime	3315
lime & shale	3390
lime	3600
lime & shale	3660
shale & chert	3700
shale	3715
sand & shale	3754
lime	3768
Arbuckle lime	3770
Total Depth	

Tops Corr.

Heebner	3240
Brown lime	3367
Lansing Kansas City	3380
Conglomerate	3653
Viola	3659
Simpson	3696
Arbuckle	3752

Small show oil DST 3515
360' fill up at 3515'

DST at 3770
Ran Schlumberger