

28- 21- 14 W


WELL LOG BUREAU- KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- SKELLY OIL CO.
Farm- Eva Smith No. 2

SEC. 28 T. 21 R. 14W
SE NW NW
990' fr NL, 990' fr WL

Total Depth. 4070'
Comm. 1-7-56 Comp. 1-22-56
Shot or Treated.
Contractor. Claude Wentworth Drlg. Co.
Issued. 2-18-56

County Stafford
KANSAS



CASING:
8 5/8" 870' cem w/700 sx

Elevation. 1942' DF

Production. Dry

Figures indicate Bottom of Formations.

dirt and sand	180
shale	270
sand	415
shale	500
red bed, shells & shale	845
shale & shells	858
anhydrite	875
anhydrite, shale & shells	1320
shale & lime	1750
lime	2195
lime and shale	3475
lime	3730
lime and shale	4005
lime	4020
fine to coarsely crystalline dolomite	4070
Total Depth	

Tops:	
Anhydrite	853
Base Anhydrite	876
Wellington	1356
Base Wellington	1833
Tarkio	2740
Near Topeka	2951
Heebner Shale	3330
Toronto Lime	3357
Douglas Shale	3374
Brown Lime	3454
Lansing Lime	3464
Base Kansas City	3712
Conglomerate	3761
Viola Lime	3994
Simpson Shale	4007
Arbuckle Lime	4015

Ran Halliburton Guard Log.