

---

# **ERNEST MORRISON**

Geologist

627 S. Lakeview • Derby, Kansas 67037 • 316/788-1150

**TRANS PACIFIC OIL CORPORATION**

**#1 REHN**

NE SW NW Section 10-T21S-R14W  
Stafford County, Kansas

# ERNEST MORRISON

Geologist

627 S. Lakeview • Derby, Kansas 67037 • 316/788-1150

## WELL DATA

Operator: Trans Pacific Oil Corporation  
Well Name: #1 Rehn  
Well Location: NE SW NW Section 10-T21S-R14W; Stafford County, Kansas.  
Contractor: Trans-Pac Drilling; Rig 1.  
Tool Pusher: Gary Pugh.  
Wellsite Geologist: Ernie Morrison.  
Elevation: 1929' K.B. and 1921' G.L.  
Spud Date: December 12, 1988.  
Surface Casing: 8 5/8" set at 370'.  
Bit Size: 7 7/8".  
Completed Drilling: December 19, 1988.  
RTD/LTD: 3742'/3742'.  
Mud: Starch/ no service mud.  
Testing: Diamond Testing: 3 tests.  
Logging: Wire-Tech: Radiation Guard Log.  
Gas Detector: Trans-Pac Drilling Inc.  
Samples: To Kansas Geological Survey Sample Library.  
Well Status: After logging the #1 Rehn was plugged.



DRILL STEM TESTS cont'

DST #3                    3646'-3695'    Simpson Sandstone    20-20-20-20

IFP: 36-36                ISIP: 52  
FFP: 40-40                FSIP: 46  
IH: 1936                    FH: 1904  
BHT: 108° F.

Recovered 5 feet of drilling mud.

GEOLOGICAL COMMENTS

The #1 Rehn ran structurally low on all potential hydrocarbon bearing zones. Small shows of oil were seen in the samples and were evaluated with the drill stem test tool and evaluated on the electric log. Due to poor reservoir development and low structural position the #1 Rehn was plugged after logging.

Respectfully submitted,

*Ernie Morrison*

Ernie Morrison 12/19/88