

6-21-15W

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY
412 Union National Bk. Bldg., Wichita, Kansas


Company - GULF OIL CORPORATION
Farm M. N. ~~Cross~~ No. 3

SEC. 6 T. 21 R. 15W
SW NE NW

Total Depth. 4415'
Comm. 12-19-47 Comp. 1-7-48
Shot or Treated.
Contractor.
Issued. 3-13-48

County. Pawnee

KANSAS



Elevation. 1977 Ind.

Production. SWDW

CASING:

8-5/8" 991' Cem. W/435' Sx.
5-1/2" 4045' Cem. W/100' Sx.

Figures Indicate Bottom of Formations.

sand	335
shale	400
sand	535
red bed	700
shale	860
sand & shale	915
shale	965
red bed	978
anhydrite	992
shale	1500
shale ~ shells	1760
lime	2015
shale	2160
lime	2305
lime & shale	3135
lime	3405
lime & shale	3435
lime	3720
lime & shale	3780
conglomerate	3835
lime & chert	4005
lime	4415
Total Depth	

Total Depth before completing
as SWDW was 3887'.

TOPS:

Lensing	3419
Case Kansas City	3668
PBC	3706
Arbuckle	3887
Pre-Cambrian	4399

Top cellar on 5-1/2"
is 8' below KB.

Formation: Top Granite 4399'