

36-21-16W

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCH

API No. 15 —

County _____ Number _____

Operator

Barnett Oil Co.

Address

411 First Nat'l Bank Bldg., Wichita, Kansas 67202

Well No.

#1

Lease Name

Prosser

OWWO

Footage Location

990 feet from XX (S) line

990

feet from XXX (W) line

Principal Contractor

Red Tiger Drilling Co.

Geologist

Alfred W. Stude

Spud Date

Re-entered
12-7-71 3-18-72

Total Depth

3912

P.B.T.D.

Date Completed

3-21-72

Purchaser

Gas


Kansas-Nebraska

S. 36 T. 21 R. 16 ~~XX~~ WLoc. C S $\frac{1}{2}$ SE

County Pawnee

640 Acres

N



Locate well correctly

1971

Elev.: Gr.

DF 1973 KB 1976

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	28#	945'		500	
		4 1/2"	9.5#	3912	Posmix	125	18% salt; 3/4% CFR2 w/1/8# nylon fibre per sks.

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
			8		3900 - 3900 1/2'

TUBING RECORD

Size	Setting depth	Packer set at

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used			Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
4/2/72		Flowing			
RATE OF PRODUCTION PER 24 HOURS	Oil 10 bbls.	Gas 1,430 MCF	Water -0- bbls.	Gas-oil ratio CFPB	

Disposition of gas (vented, used on lease or sold)	Producing interval(s) Simpson

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

Barnett Oil Company

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.

Gas

Well No.	1	Lease Name	Prosser OWWO				
S	36	T	21	R	16	XXX	W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
<p>See report filed previously covering dry hole completed 12/18/71.</p> <p>Re-entered 3-18-72 - took Straddle test:</p> <p>3899-3903 - 0 - 60"; SI - 60"; 0 - 120"; SI - 60"; immediate strong blow, GTS in 1"; gauged 1/4 mmcf, increased to 2.8 mmcf in 60". Second opening gauged 3.1 mmcf, increased to 3.7 mmcf rec. 90' free oil, 40°; 10' water.</p> <p>IFP - 204# ISIP - 1273# FFP - 427# FSIP - 1245#</p>				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received SEP 1973	BARNETT OIL COMPANY By: <i>W. Gould</i> Signature
RECEIVED STATE GEOLOGICAL SURVEY OF KANSAS	Partner
	Title
	Date

August 30, 1973