

36-21-16W

WELL LOG BUREAU--KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas


Company- IRON DRILLING COMPANY
Farm- F. Prosser "B" No. 3

SEC. 36 T. 21 R. 16W
SE SW SW

Total Depth. 4159
Comm. 8-28-52
Shot or Treated.
Contractor.
Issued. 10-18-52

Comp. 9-15-52

County Pawnee KANSAS



Elevation. 1980

Production. Dry

CASING:

8 5/8" 977' com. w/450 sx
5 1/2" 4038' com. w/125 sx

Figures Indicate Bottom of Formations.

surface clay & sand	40
sand	120
shale & shells	250
shale blue	310
red bed	392
sand	490
red bed	845
red bed & shells	849
anhydrite	965
shale	1200
shale & shells	1350
salt & shale	1450
shale	1680
shale & shells	1835
lime & shale	1910
lime & shale	2073
lime	2170
shale & lime	2325
lime	2342
lime & shale	2750
shale	2870
lime & shale	3130
chert	3150
lime & shale	3179
lime	3487
lime & shale	3510
lime	3831
cherty congl.	3861
congl.	3874
shale	3929
lime	3940
arbuckle	3991
lime	4076
cherty lime	4095
lime	4159
Total Depth	

Scout Tops:

Anhydrite	849
Brown Lime	3486
Lansing	3495
Arbuckle	3991