

Henneigh #1

Schilo Petroleum Co. #1 Henneigh

SE-SE ~~NW~~ 13-215-16W

Well Comp. 4-27-48

Plug Comm. 4-27-48

Plug Comp. 4-27-48

8 7/8 @ 965' 500 sx cement.

3880-2040 Hvy Mud.

2040-1990 100 sx cement (Holliburton Pump truck)

1990-202 Hvy Mud

202-198 Wood bridge

198-100 Hvy Mud & CS Halls.

100-2 Cement.

Gore #1

Nadel & Gussman #1 Gore NE-SE-SE 13-215-16W

8 7/8 @ 966' 450 sx

5 1/2 @ 3597' 100 sx

Comm. 5-26-54 Comp. 6-9-54

Plug Comm. 6-22-58

" comp. 6-27-58 Top. Perf. 3812

Plugged off bottom of sand to 3800' & dumped 5 sx cement. Shot 5 1/2" esp at 3,140'. Layed down pipe. Mudded to 240'. Set rock bridge & dumped 20 sx cement. Filled hole w/ mud to 40'. Set rock bridge & mixed 10 sx cement for esp on well.

Pulled 3,140' of 5 1/2"

Gore #2

Nadel & Gussman #2 Gore NW-NW-SW 13-215-16W

Comm. 11-24-57 Comp 12-6-57

8 7/8 @ 975' 450 sx cement

T.D. 3850

Plug Comm. 12-6-57

Plug Comp. 12-6-57

Filled hole w/ hvy mud to 350' set plug, 1/2 sack halls & 25 sx cement thru drill pipe. Mud to 40'; set plug, 1/2 sack halls & 10 sx cement.