


FARM J. A. Boyd "A" NO. 1

TOTAL DEPTH 3994'  
 COMM. 4-6-51 COMP. 4-23-51  
 SHOT OR TREATED  
 CONTRACTOR  
 ISSUED 6-16-51



CASING

8 5/8" 1127' cem w/600 sxs.

ELEVATION 2098(m)  
 2100 RDB

PRODUCTION dry

FIGURES INDICATE BOTTOM OF FORMATIONS

surface clay	105
shale	375
sand rock, iron	385
sand shale	520
red bed, shale	765
red bed	950
red bed, shells	1122
anhydrite	1150
red bed	1420
shale, shells	1860
shale, lime	1975
sandy lime	2100
lime	2265
sandy lime	2340
shale, lime	2380
lime	2550
lime, shale	2680
shale	2990
shale, lime	3220
shale	3280
lime, shale	3345
lime	3390
lime, shale	3460
lime	3510
lime, shale	3597
lime	3617
lime, shale	3645
lime, porous, NS	3725
lime, shale	3760
lime	3810
lime, shale	3850
lime	3900
conglomerate	3930
shale	3951
dolomite, fair porosity, NS	3963
Lime, dolomite, vugular	3966
Porosity Odor	
Dolomite Lime	3994
Total depth	
Tops:	
Arbuckle	3951
Lansing K. C.	3597

Schlumberger Electric Log to TD  
 Total depth:  
 By Schlumberger 3994  
 By Rotary Drill 3994