

WELL LOG BUREAU - KANSAS GEOLOGICAL SOCIETY.
412 Union National Bank Bldg, Wichita, Kansas.


18-21-17W

CITIES SERVICE OIL CO.
Evans No. 1.

SEC. 18 T. 21 R. 17 W.
NE SE SW
990' N. & 330' W. of S $\frac{1}{4}$ Cor.

Total Depth. 4038 Rot. T.D. = 4034 SLM
Comm. 4-19-42 Comp. 5-18-42
Shot or Treated. None
Contractor. Holm Drilling Co.
Issued. 7-4-42

County. Pawnee



CASING.

12 $\frac{1}{2}$ " 98' cemented.
8 $\frac{5}{8}$ " 1085' cemented.
5 $\frac{1}{2}$ " 4034' cemented.
(Pld 3189' of 5 $\frac{1}{2}$ ")

Elevation.

Production. Dry.

Figures Indicate Bottom of Formations.

surface rock & sand	87
lime med	98
shale & shells	330
shale	425
shale and shells	488
sand and shells	550
sand	625
shale red	670
sand	685
shale red	729
sand	734
shale red	885
red shale & shells med	1057
shale red	1075
lime	1108
shale	1145
shale dark and shells	1470
shale blue sdy	1590
shale blue & shells	1740
shale and salt&shells	1810
lime light med	1840
shale and shells	1910
lime light med	2030
lime broken med	2050
lime light hard	2120
lime dark hard	2143
lime med	2163
lime broken med	2275
lime light hard	2320
lime broken med	2390
lime light med	2620
lime light broken	2655
lime light med	2830
lime broken	2858
lime light med	2906
lime broken	2964

lime light med	3012
lime broken	3025
lime light hard	3338
lime light med	3405
lime light hard	3454
lime light med	3481
lime broken	3533
lime	3608
lime soft	3622
lime hard	3655
lime light med	3738
lime light hard	3799
lime light med	3848
lime light hard	3860
lime light med	3922
shale blue	3990
shale gray hard	4007
shale gray soft	4026
lime	4028
granite	4038

4038 Rot. T.D. = 4034 SLM

Total Depth.

Corr. Top Reagan	3892
Corr. Top Granite wash	4007
Corr. Top Granite	4028
Penetration	6'

Top cement 4000' SLM May 23, 1942
Perf. with 11 shots 3890-3900.
2400' sulphur water in $\frac{1}{2}$ hour.
2700' sulphur water in $\frac{3}{4}$ hour.