

IMPORTANT
Kans. Geo. Survey request
samples on this well.

Released 2-24-75
CONFIDENTIAL

S. 29 T. 21 R. 17 ^E_W

Loc. C SW

County Pawnee

640 Acres
N

Locate well correctly
2040

Elev.: Gr.

DF _____ KI _____

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

LINER RECORD

PERFORATION RECORD

TUBING RECORD

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used

Depth interval treated

Frac w/15,000 gal. KCL water & 15,000# sand

2013 - 2020

INITIAL PRODUCTION

Date of first production

Producing method (flowing, pumping, gas lift, etc.)

flowing

**RATE OF PRODUCTION
PER 24 HOURS**

이

Gas

Water

Gas-oil ratio

bbls.

MCF

bbbs

CEPR

Disposition of gas (vented, used on lease or sold)

Producing interval (s)

2013 - 20

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Beren Corporation		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 1	Lease Name Marlyn	
S 29 T 21 S R 17 ^{XB} _W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
NO DRILL STEM TESTS			Anhydrite B. Wellington Herington	1041-63 1992 2011

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



Don W. Beauchamp
Signature
Don W. Beauchamp - Geologist
Title
1-28-74
Date

31115

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

29-21-17W

API#15-145-20304

WELL LOG ----- MARLYN #1

Located: C SW, Section 29-21S-17W, Pawnee County, Kansas

OWNER: Beren Corporation

ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

COMMENCED: October 7, 1973

COMPLETED: October 11, 1973

TOTAL DEPTH: 2014'

LOG

CASING RECORD

0 - 86 Clay and Shale
86 - 735 Shale and Sand
735 - 1041 Shale
1041 - 1063 Anhydrite
1063 - 1300 Shale
1300 - 2014 Lime and Shale

Ran 24 joints 7", 20# casing, 725' pipe set at 726.50' G.L. Cemented with 175 sacks 60/40 Pozmix with 4% gel, 3% cc, followed with 75 sacks 60/40 Pozmix with 2% gel, 3% cc. Plug down at 11:45 AM, 10-8-73.

Ran 63 joints 4 1/2", 9.5# used seamless casing, 2027' pipe set at 2013' G.L. Cemented with 125 sacks 60/40 Pozmix, 18% salt saturated. Plug down at 10:45 AM, 10-11-73.

