

State Kansas County Pawnee

Company Messman-Rinehart Oil Co. Well No. 1

Farm Mull

Survey _____

Block No. _____ Sec. 17 Twp. 21 S Range 15 W

Co-Ord. _____ Elev. 1963' K/B
1960' D/f

C. W/2 W/2 NW/4 M-R Rig

										12.5%	- E. G. Bradley
*										25%	- Rio Hondo Oil & Dev. Co.
										25%	- Chicago Group
										12.5%	- Simon Lebow
										25%	- Kansas Western Gas Co.

3850 Arbuckle test to be completed on or before 11/5/60

NOTE: Show Sketch of Lease and Well Location in Above Space

1320 Ft. from N. Line _____ Ft. from S. Line _____

330 Ft. from W. Line _____ Ft. from E. Line _____

Date	Depth	
10/5/60		M.I.R.T.
10/6		Spud - 8-5/8" @ 682' w/300 sx cem., 6 gel., 6 c.c.,
		P.D. @ 6:00 p.m. 10/6/60
10/9	2160	Drlg. (#2 @ 1850)
		(#3 @ 2180)
10/10	2530	Drlg. (#4 @ 2500)
10/11	2920	Drlg. (#5 @ 2900)
10/12	3210	Drlg. (#6 @ 3210)
10/13	3435	Drlg.

692012

Date	Depth	
	3318	Heebner (-1355)
	3419	Brown Lime (-1456) (Circ. for KC)
	3427	Lansing (-1464)
10/14	3600	Drig. (#7 @ 3450) (#8 @ 3618)
	3710	Conglomerate (-1747)
10/15	D.S.T. #1	- 3729-55 - Op 1 hr., GTS in
		5", Ga. 49,000 cf - 10"
		Decr. to 40,000 cf in 60"
		Rec. 60' mud, ISIP 1190#,
		FSSIP 1100#, FP 50-50#
	3800	Arbuckle (-1837) 2' higher than
	D.S.T. #2	- 3802-17 - Op 1 hr., str. bl., No. 1 Schmitt
		Rec. 2600' sulphur wtr.,
		ISIP 1200#, FSIP 1180#,
		FP 750-1180#
	D.S.T. #3	- 3820-37' -GTS in 12", Died in
		60", Rec. 2650' sulphur wtr.,
		sli gas & oil-cut ISIP 1240#,
		FSIP 1200#, FP 530-1160#
	3837	R.T.D. (No log)
		D & A 10/17/60