

SANDRAGO

Form 113 50M 6-47-41683-D

State Kansas County StaffordSec. 12 Twp. 21 Rng. 11w Elev. 1815Company Phillips Pet. Co.Well No. 15 Name KleinLocation NW 1/4 NW 1/4Feet from lines: N. S. E. W. Spud 8-15-47 Completed 11-5-47T. D. 3503 Casing 5" 3478'PB 3437Comp. Perf. 2 1/2" 3248-3410Pay 3248-3410 in lens.I. P. 625 BOPD, no wtr.Choke T. P. C. P. G. O. R. Grvty.

DATE	REMARKS
11-5-47	Heeb. 3030, Brn. lm. 3154, Lens. 3171 Arb. 3477, GSO 3374-18 @ 3325- 32, DST 3325-32, open 40 min., rec. 300' oil, BHP 950#/10 min.

DATE	REMARKS
DST 3343-53,	open 40 min., rec. 125' fluid, 113' O & GCM & 10' oil, BHP
500#/10 min.,	DST 3343-53, open 40 min., rec. 123' fluid, DST 3372-79,
open 40 min.,	rec. 90' oil, no wtr. DD 3485 RTD, DP TD, lat. 8 GO/2 hrs.
8:00 / 1 GW/2,	B/18 GOPH/4, 500 A, Grav. 31.3, Swb/20 BO / 7 HW/3
TD 3487,	2000 A, P/21 BO/5, P/2h BO / 5 HW/6, P/6h BO, 20% wtr/2h
P/49 HW/2h,	gr. out 18% wtr. DD 3503, Swb/6h BF/6 hrs. to btm.
PB 3432,	52 % 3397-3410, B/5h GO / no wtr/1, Swb/25 BO/12, grav. 37.6
1500 A,	Swb/16h BO/9, LWplug 3390, 60 % 3344-59, Swb/3h BO/30 min.
Swb/57 BO/4,	56 % 3322-36, Swb/62 BO/3 1500 A, Swb/88 BO/5, Swb/86 BO/5,
drove plug to 3430,	set plug 3288 7h / 3248-72, Swb/165 BO/7, drove plug to 3437 PBD, P/209 BO/8
Phy. pot. 627 BOPD,	no wtr. COMPLETE
Combank	UNITS IN USE
2nd	1st 3rd 4th 5th 6th
2nd	Comd
	718819