

27-21-2W

Company - P. G. REYNOLDS
Farm - Goering No.1.

SEC. 27
NW SE NW


T. 21

R. 2 W

Total Depth. 3527'
Comm. 10-12-44 Comp. 11-2-44
Shot or Treated.
Contractor. Veeder Sup&Dev.Co.
Issued. 11-25-44

County.

McPherson
KANSAS



CASING:
8 5/8" 242'

Elevation _____

Production

Dry

Figures Indicate Bottom of Formations.

soil - sand	55
clay - sand	120
sand - shale	200
shale sticky	235
W.O.C.	
shale	321
anhydrite	595
lime & shale	720
lime	815
lime & shale	1075
shale & shells	1420
shale & lime	1540
shale & shells	1745
lime	1835
lime & shale	1970
lime	2090
lime brkn	2121
shale	2240
shale & lime	2374
lime	2437
lime & shale	2445
lime	2520
lime brkn	2590
lime	2635
lime brkn	2740
shale	2760
shale & lime	2830
shale	2900
lime & shale	2993
chert & lime	3003
shale	3009
congl	3025
lime	3320
shale, lime sdy	3410
shale & lime	3485
shale	3502
lime	3527
Total Depth	

Top Lansing 2365
Top Miss. lime 3009
HDS 13010-51, open 2.5 min. rec.
240' rot. mud, no shows
Base Miss. 3283
Top Dunton 3393
Top Viola 3501
slt. show oil 3009-51
Parous 3013-26 no staining or oil
" 3029-38 very slt. show of oil
" 3041-46 " " " "
34" 11, some por & very lg stain