

A-6-32

2902 EDF

MAP NO. K-52ELEV. 2900 GLSTATE Kansas COUNTY Finney SEC. 20 Twp 21 S Rge 32 WOPERATOR Sinclair Oil & Gas LOC. C SW/4WELL NO. 1 FARM NAME Lucille Archer Unit FT. FROM _____ LINE _____Hugoton (PD 2750) FT. FROM _____ LINE _____FR. 10-61 SPUD 4-20-61 COMP. 5-25-61CONT./GEOL. Holm Drilling Company Don Calvin/Geol

NAME PRODUCING INTERVAL FROM - TO PERF. W/HOLES TREATMENT RECORD

a Hollenberg, 2630-88 104 500 Ac-F/30X30b Herrington &c Krider

d _____

d I. P. OIL/DIST. WTR. 48 BL GAS 1,500 M.C.F.P.D. CHK. 3/4" HRS. 24

b " " " " " "

c " " " " " "

d _____

D & A ()

SIP# _____ FI TP # 220 FI CP# 320 SIBHP _____GOR. _____ GR. _____ PBDT 2730 TD 2765

CASING - CEMENT RECORD

SIZE DEPTH W/SAX. SIZE DEPTH W/SAX.

8-5/8" 319 2752" 2763 150OPERATOR Sinclair O & G WELL NO. 1 Lucille Archer Un ELEV. 2902 EDF

SAMPLE TOPS DEPTH SUB SEA ELEC. TOPS DEPTH SUB SEA

Herrington 2659 Hollenberg 2632Krider 2680 Herrington 2659Winfield 2714 Krider 2680Winfield 2714

Spud 4-20-61. 8-5/8" @ 319 w/275 sx.

RTD 2760 in Permian, logs (GRN) to 2765. 5 1/2" @ 2763 w/150 sx. CO to 2730.

P/24/Kri/2682-88. 500 MA. Swb 5 BLPH/NS. Frac 10,000 Ac X 10,000 sd. Swb & flod 97 BL w/125 MCF/13 hrs, 3/4" ck, FTP 25, FCP 450. Swb pt 1d, KO, flod 3 BL/8 hrs, Ga 600 MCF, 3/4" ck, FTP 150, FCP 250.

P/40/Herr/2659-69, 40/Hol/2630-40. Frac 20,000 gel Ac X 20,000 sd w/60 sealer balls. Swb & flod 147 BL w/369 MCF/24 hrs, 3/4" ck, FTP 25, FCP 250. Ga 1500 MCF + 4 BLPH, 3/4" ck, FTP 75, FCP 250, from 2630-88, Ga 458 MCF + 2 BLPH/3 hrs, 1/2" ck, FTP 220, FCP 320.

IP ga 1500 MCF + 48 BLPH, 3/4" ck, FTP 220, FCP 320 from Hollenberg, Herrington & Krider (2630-88).

COMPLETE 5-25-61

LIBERAL TOPS

est 2902 DF

Winfield 2714 (+188) ϕ 1,500 MCF + 48 BLPD
TD 2765