

15-21-21W


**WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY**  
508 East Murdock,                      Wichita, Kansas

Company- **BEARDMORE DRILLING**  
Farm- Huling                      No. 2

SEC. 15              T. 21              R. 21W  
50' W of C SE SW

Total Depth. 4660'  
Comm. 10-3-63                      Comp. 10-22-63  
Shot or Treated.  
Contractor. Gabbert - Jones Inc.  
Issued. 3-14-64

County HODGEMAN  
KANSAS



**CASING:**

Elevation. 2134 DF'

8" 1278' cem w/600 sx  
5" 4336' cem w/125 sx

Production. 106 BOPD

Figures Indicate Bottom of Formations.

9-30-63 to 10-2-63 C SE SW  
clay 40  
sand & shale 875  
sand 900  
red bed, shale & shells 1195  
shale 1264  
shale 1278  
Total Depth

DST # 1 4259-4576

DST #2 4277-4286

DST # 3 4287-4301

DST # 4 4302-4321

Oct. 3, 1963 to Oct. 22, 1963  
Moved rig 50' W of C SE SW

*(See Top Card)*

Clay 120  
sand 135  
sand & shale 280  
shale 488  
red bed 575  
shale & shells 600  
anhydrite 620  
shale 705  
sand 870  
red bed, shale & shells 1000  
red bed 1260  
anhydrtie 1320  
shale & red bed 1780  
shale & shells 2065  
shale & lime 2330  
lime & shale 2340  
lime 2405  
lime & shale 2969  
shale chalk 3130  
shale & lime 3280  
shale w/lime streaks 3350  
lime & shale 3893  
lime 4286  
lime & chert 4311  
lime 4321  
cherty lime 4380  
lime 4560  
sand & lime 4575  
cherty lime 4660  
Total Depth

**TOPS: LOG**

Blaine 605  
Base Blaine 614  
Stone Corral 1257  
Base Stone Corral 1279  
Heebner shale 3616  
Lansing 3670  
Base Kansas City 4022  
Marmaton 4030  
Fort Scott limestone 4180  
Cherokee shale 4202  
Mississippi Osage 4252  
Kinderhook limestone 4320  
Viola 4388  
Simpson 4544  
Arbuckle 4576