

PS

State Geological Survey

SIDE ONE

WICHITA, BRANCH

AFFIDAVIT OF COMPLETION FORM

22-21-214 P1
(REV) ACO-1

This form shall be filed in duplicate with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ten days after the completion of the well, regardless of how the well was completed.

Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on side one will be of public record and side two will then be held confidential.

Circle one: Oil, Gas, Dry, SWD, OWWO, Injection. Type and complete ALL sections. Applications must be filed for dual completion, commingling, SWD and injection, T.A.

Attach wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.).
KCC # (316) 263-3238. (Rules 82-2-105 & 82-2-125)

OPERATOR GALLOWAY DRILLING CO., INC
340 Broadway Plaza Bldg.
ADDRESS 105 So. Broadway
Wichita, KS 67202

API NO. 15-083-20.971

COUNTY Hodgeman

FIELD Eakin NW

PROD. FORMATION none

LEASE Blount

WELL NO. 5


WELL LOCATION N/2 N/2 SE

 Ft. from Line and

 Ft. from Line of

the SEC. 22 TWP. 21 RGE. 21 W

WELL PLAT



KCC
KGS ☒
(Office Use)

**CONTACT PERSON Earlene M. Lumry
PHONE 316-262-1793

PURCHASER none

ADDRESS

DRILLING Galloway Drilling Co., Inc.
CONTRACTOR
ADDRESS same as above

PLUGGING Allied Cementing
CONTRACTOR Box 31
ADDRESS Russell, KS

TOTAL DEPTH 4343 PBTD

SPUD DATE 4/2/82 DATE COMPLETED 4/9/82

ELEV: GR DF KB 2136

DRILLED WITH (CABLE) (ROTARY) (AIR) TOOLS

Amount of surface pipe set and cemented 1267' DV Tool Used? NO

A F F I D A V I T

STATE OF KANSAS, COUNTY OF SEDGWICK SS, I,

Jay H. Galloway OF LAWFUL AGE, BEING FIRST DULY SWORN UPON HIS OATH,

DEPOSES THAT HE IS President (~~FOR~~)(OF) Galloway Drilling Co., Inc.

OPERATOR OF THE Blount LEASE, AND IS DULY AUTHORIZED TO MAKE

THIS AFFIDAVIT FOR AND ON THE BEHALF OF SAID OPERATOR, THAT WELL NO. 5 ON

SAID LEASE HAS BEEN COMPLETED AS OF THE 9 DAY OF April, 19 82, AND THAT

ALL INFORMATION ENTERED HEREIN WITH RESPECT TO SAID WELL IS TRUE AND CORRECT.

SIDE TWO

Galloway Dr 1/4

WELL LOG

#5 Blount

P1

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Anhydrite	1269	+867		22-21-2/w
Heebner	3663	-1527		
Lansing	2717	-1581		
B/KC	4084	-1948		
Ft. Scott	4243	-2107		
Cherokee	4266	-2130		
Mississippi	4328	-2202		
RTD	4343			
DST #1 4288-2333 15-45-90-45, 240' wtry mud, 120' muddy water, IBHP 53-64, IFP 1348-1294, FFP 85-208.				

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set in O.D.	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 $\frac{1}{4}$	8 5/8	24#	1273'	Common	500	60-40 POZ

LINER RECORD

PERFORATION RECORD

none	Top, ft	Bottom ft	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

none	Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD