

JAN 31 1970

STERLING DRILLING COMPANY
P. O. Box 129
Sterling, Kansas 67579

24-21-21W
NW SW SW

Elv. 2122 KB

WELL LOG ----- THOMPSON #1

Located: NW SW SW, Section 24-21S-21W, Hodgeman County, Kansas

OWNER: Beacon Resources Corporation and Sterling Drilling Company
ROTARY DRILLING CONTRACTOR: Sterling Drilling Company

Dry/miss

COMMENCED: December 10, 1969

COMPLETED: December 23, 1969

TOTAL DEPTH: 4340'

LOG

CASING RECORD

0 - 235	Surface Clay Sand
235 - 265	Blue Shale
265 - 500	Surface Shale
500 - 597	Shale
597 - 616	Anhydrite
616 - 935	Shale
935 - 1540	Shale - Red Rock
1540 - 1945	Shale and Red Bed
1945 - 2008	Shale and Lime
2008 - 3170	Lime
3170 - 3303	Shale
3303 - 3530	Lime
3530 - 3690	Shale and Lime
3690 - 4295	Lime
4295 - 4340	Miss.

Ran 8 5/8" Casing - Drilled 12 1/4" hole
to 616', ran 605' - 8 5/8" casing, cemented
at 615' K.P. with 350 sacks Quikset. Plug
down at 3:00 PM 12-11-69.



anhy + 1254
Hebner 3649
Loring 3706
Cherokee 4240
Mississippi 4287

Plugged