

D. R. Lauck Oil Company, Inc.
and Sunray Mid-Continent Oil Company

Titus #3

NE NW NE 21-21S-14W
Stafford County, Kans

Commenced: October 11, 1956
Completed: October 23, 1956

Casing Record: 858' 8 5/8" cem. w/425 sx
3703' 5 1/2" cem. w/100 sx

Elevation: GR 1936; DF 1938; KB 1940;

Drillers Log

		Tops	
		Sample	Halliburton
Sand & clay	230		
blue shale	310	Heebner	3272-1332
Dakota sand	415	Douglas	3315-1375
Red Bed & Shale	856	Brown Lime	3391-1451
Anhydrite	880	Lansing KC	3403-1463
Red bed & shale	1360	Base KC	3636-1695
shale & shells	1690	Conglomerate	3666-1726
lime & shale	2095	Viola	3674-1734
lime	2170	Simpson Shale	3734-1794
lime & shale	2650	Simpson Sand	3752-1812
shale & shells	2770	Arbuckle	3786-1846
lime & shale	3000	Rotary TD	3800-1860
lime	3273	Halliburton logging tool left in hole	
Heebner	3277		
Lime	3280	DST #1 (M-D)	3517-3533 open 1 hr;
lime & shale	3345		good blow 1 hr; gas to surface;
shale	3392		20 min; recov. 610' gassy oil
Lime	3685		IFP 80#; FFP 240#; BHP 880# in
Viola	3715		30 min.
Simpson	3740		
Lime & sand	3756	DST #2 (M-D)	3555-3575 open 1 hr;
shale & sand	3800		weak steady blow 1 hr; recov.
Rotary Total Depth	3800		215' salt water; IFP 0#;
			FFP 130#; BHP 1110# in 30 min.

The above is a true and correct copy of the Titus #3 well, to the best of my knowledge and belief.

John H. Knightley
John H. Knightley

DST #3 (M-D) 3739-3756 open 1 hr; weak steady blow 1 hr. recov. 120' watery mud; IFP 0#; FFP 80#; BHP 820# in 30 min.

Subscribed and sworn to before me this 6th day of November, 1956.

Elizabeth Gay
Elizabeth Gay
Notary Public

My commission expires: Sept. 14, 1959

RECEIVED

NOV 6 1956

Sunray Mid-Continent Oil Company
Scouting Department