

15-083-20385

6-21-22W ✓

State Geological Survey
WICHITA, BRANCH

D R I L L E R S L O G

#1 Carpenter

CASING:
305.31' of used 8-5/8"
surface casing.

COMPANY: Twin Western Resources, Inc.

CONTRACTOR: Strata Drilling Company

COMMENCED: December 12, 1974

COMPLETED: December 20, 1974

DESCRIPTIONS:
C/SW NE
Section 6-21-22W
Hodgeman Co., Kansas

TOTAL DEPTH:
4498'

D. & A.

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>REMARKS</u>
Surface Soil & Post Rock	0	90	Ran 305.31' of used 8-5/8" surface casing; set and cemented at 310' with 185 sacks of common cement, 2% gel and 3% C. C. Plug down at 5:00 A. M. December 13, 1974.
Shale	90	430	
Shale, Sand & Red Bed	430	1230	
Shale w/Sand Streaks	1230	2165	
Shale & Lime	2165	2275	
Lime & Shale	2275	2700	
Lime	2700	2910	
Lime & Shale	2910	4325	
Shale	4325	4446	
Lime & Shale	4446	4498	
			Ran electric log.

ROTARY TOTAL DEPTH: 4498'

D. & A.



Plugged hole as follows: Plugged at 450' with 50 sacks of 60-40 pozmix; plugged at 240' with 25 sacks of 60-40 pozmix; plugged at 40' with hulls and 10 sacks of 60-40 pozmix. Plug down at 1:30 P. M. December 20, 1974.

STATE OF KANSAS)
COUNTY OF BARTON) ss.

I certify that this is a true and correct copy of the above log to the best of my knowledge.

STRATA DRILLING COMPANY

Kenneth J. Link