

7-21-22W

Ind

TYPE



AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

Compt. _____

SIDE ONE

Two (2) copies of this form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within thirty (30) days after the completion of a well, regardless of how the well was completed.

F Attach separate letter of request if the information is to be held confidential. If confidential, only file one copy. Information on Side One will be of public record and Side Two will then be held confidential.

Applications must be made on dual completion, commingling, salt water disposal, injection and temporarily abandoned wells.

C Attach one copy only wireline logs (i.e. electrical log, sonic log, gamma ray neutron log, etc.). (Rules 82-2-105 & 82-2-125) KCC# (316) 263-3238.

LICENSE # 5053 EXPIRATION DATE 6-30-83

OPERATOR PETRO-DYNAMICS CORP. API NO. 15-083-20,031

ADDRESS 555 N. Woodlawn, Bldg. 1 - Suite 207 COUNTY Hodgeman

Wichita, Kansas 67208 FIELD

** CONTACT PERSON Dick Flaker PROD. FORMATION N/A

PHONE (316) 681-1685

PURCHASER LEASE Bamberger

ADDRESS State Oilfield Services WELL NO. 1

WELL LOCATION C N2 SW NW

DRILLING KANDRILCO, Inc. 1650 Ft. from North Line and

CONTRACTOR ADDRESS 555 N. Woodlawn, Bldg. 1 - Suite 207 660 Ft. from West Line of

Wichita, Kansas 67208 the NW (Qtr.) SEC 7 TWP21S RGE 22 (W).

PLUGGING Sun Oilwell Cementing

CONTRACTOR ADDRESS P.O. Box 169

Great Bend, Kansas 67530

TOTAL DEPTH 4510 PBTD

SPUD DATE 12-13-82 DATE COMPLETED 12-23-82

ELEV: GR 2258 DF 2263 KB 2266

DRILLED WITH ~~(XXXXX)~~ (ROTARY) (XXX) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

Amount of surface pipe set and cemented 479.95' DV Tool Used? No

THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Gas, Shut-in Gas, Dry Disposal, Injection, Temporarily Abandoned, OWWO. Other

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

WELL PLAT

(Office Use Only)

◆			

KCC
KGS

SWD/REP
PLG.

A F F I D A V I T

DICK FLAKER, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

(Signature)

(Name)

SIDE TWO

ACO-1 WELL HISTORY

OPERATOR PETRO-DYNAMICS CORP. LEASE Bamberger SEC. 7 TWP. 21S RGE. 22 (W)

FILL IN WELL INFORMATION AS REQUIRED: WELL NO. 1

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Check if no Drill Stem Tests Run.				
Shale	0	495	HEEBNER	3771' (-1505
Sand & Shale	495	1295	LANSING	3819' (-1553
Redbed	1295	1469	STARK SH.	4077' (-1811
Anhydrite	1469	1510	MARMATON	4185' (-1919
Shale	1510	2120	PAWNEE	4254' (-1988
Line & Shale	2120	4510	FT. SCOTT	4343' (-2077
R.T.D.	4510		CHEROKEE SH	4367' (-2101
			MISS CONG.	4426' (-2160
			MISS WARSAW	4452' (-2185
			MISS OSAGE	4463' (-2197
			LTD/RTD	4510' (-2244
DST #1, 4335'-43375' (Ft. Scott)				
IFP/30": 55-55				
ISIP/60": 914				
FFP/15": 66-66				
FSIP/30": 420				
Rec. 10' of mud				
DST #2, 4390'-4460' (Miss)				
IFP/30": 71-71				
ISIP/60": 986				
FFP/45": 71-71				
FSIP/90": 906				
Rec. 15' drilling mud				
Wellsite Geologist: Philip Hart				
If additional space is needed use Page 2, Side 2				

Report of all strings set -- surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	483.95GL	Common	275	2% gel, 3% CaCl

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD					
Size	Setting depth	Packer set at			