


10-21-22W

Total Depth. 4730'
Comm. 10-10-61 Comp. 10-29-61
Shot or Treated.
Contractor. Garvey Drlg. Co.
Issued. 3-10-62

County Hodgeman
KANSAS



CASING:
9 5/8" 262' cem w/175 sx.

Elevation. 2189' RB

Production. Dry

Figures Indicate Bottom of Formations.

blue shale	262
shale & red bed	720
Anhydrite	732
shale	805
sand	1020
shale	1075
sand & shale	1350
Anhydrite	1383
shale	1935
shale & lime	2335
lime	2650
shale & lime	3010
shale	3390
shale & lime	3500
lime & shale	3575
shale & lime	3665
lime	4318
chert	4335
lime & chert	4368
chert	4397
lime	4445
lime & chalk	4490
lime	4515
chert & lime	4531
dolomite & chert	4548
lime & chert	4585
chert & lime	4637
lime & chert	4685
lime	4718
Granite Wash	4730
Total Depth	

TOPS:	
Kansas City	3715
Mississippian	4318
Viola	4451

TOPS: SCOUT	
Heebner	3670
Toronto	3693
Douglas	3704
Lansing	3725
Base Kansas City	4010
Marmaton	4079
Fort Scott	4156
Cherokee Shale	4220
Morrow	4297
Osage	4336
Kinderhook	4403
Viola	4482
Arbuckle	4626