

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock,  
Wichita, Kansas


16-21-22W

Company. PICKRELL DRILLING CO.  
Farm. Wieland "B" No. 2

SEC. 16 T. 21 R. 22W  
C NW SE

Total Depth. 4368'  
Comm. 8-15-61 Comp. 8-27-61  
Shot or Treated.  
Contractor.  
Issued. 11-25-61

County Hodgeman  
KANSAS



CASING:  
8 5/8" 272' cem w/155 sx.  
5 1/2" 4355' cem w/100 sx.

Elevation. 2263' RB

Production. 42 BOPD

Meas. from top of RB. Figures Indicate Bottom of Formations.

|                      |          |
|----------------------|----------|
| post rock & clay     | 75       |
| black shale          | 150      |
| blue shale           | 215      |
| shale                | 340      |
| shale & sand         | 365      |
| shale                | 590      |
| red bed & shale      | 800      |
| shale & shells       | 830      |
| red bed              | 895      |
| sand & shale         | 1090     |
| red bed & shale      | 1435     |
| Anhydrite            | 1465     |
| shale & shells       | 1900     |
| lime & shale         | 2340     |
| lime                 | 2695     |
| lime & shale         | 3585     |
| sand, lime & shale   | 3725     |
| shale & lime         | 3885     |
| lime                 | 3975     |
| lime & shale         | 4261     |
| Ft. Scott            | 4292     |
| lime & shale         | 4353     |
| Mississippi Dolomite | 4357     |
| Mississippi Chert    | 4365 RTD |
| chert                | 4368     |
| Total Depth          |          |

|                  |      |
|------------------|------|
| TOPS: SCOUT      |      |
| Ft. Scott        | 4261 |
| Mississippi      | 4353 |
| Mississippi Por. | 4357 |