

TYPE

AFFIDAVIT OF COMPLETION FORM

ACO-1 WELL HISTORY

1110

SIDE ONE

25-21-2300
Compt
DOCKET NO. NP

(Rules 82-3-130 and 82-3-107)

This form shall be filed with the Kansas Corporation Commission, 200 Colorado Derby Building, Wichita, Kansas 67202, within ninety (90) days after the completion of a well, regardless of how the well was completed.

FOR INFORMATION REGARDING THE NUMBER OF COPIES TO BE FILED AND APPLICATIONS REQUIRING COPIES OF ACO-1 FORMS SEE PAGE TWO (2), SIDE TWO (2) OF THIS FORM.

F Letter requesting confidentiality attached.

C Attach ONE COPY of EACH wireline log run (i.e. electrical log, sonic log, gamma ray neutron log etc.)***Check here if NO logs were run_____.

PLEASE FILL IN ALL INFORMATION. IF NOT AVAILABLE, INDICATE. IF INFORMATION LATER BECOMES AVAILABLE, SUBMIT BY LETTER.

LICENSE # 5760 EXPIRATION DATE June 30, 1984

OPERATOR IREX Corporation API NO. 15-083-21,105

ADDRESS 1670 Broadway, Suite 3301 COUNTY Hodgeman
Denver, CO 80202 FIELD

** CONTACT PERSON Mr. Bill Bayliff PROD. FORMATION
PHONE Indicate if new pay.

PURCHASER LEASE Law

ADDRESS WELL NO. 1

RECEIVED

FEB 09 '84

DRILLING H-30, Inc. IREX Corp. Ft. from Line and

CONTRACTOR PRODUCTION Department Ft. from Line of

ADDRESS 251 N. Water, Suite 10
Wichita, KS 67202 the NE (Qtr.) SEC25 TWP21S RGE 23 (W).

PLUGGING Halliburton Services (Office Use Only)

CONTRACTOR 410 Union Center Bldg.
ADDRESS Wichita, KS 67202
KCC
KGS
SWD/REP
PLG.
NGPA

TOTAL DEPTH 4650' PBTD

SPUD DATE 12/14/83 DATE COMPLETED 12/29/83

ELEV: GR 2317' DF KB 2324'

DRILLED WITH ~~KABKEX~~ (ROTARY) (~~KKEX~~) TOOLS.

DOCKET NO. OF DISPOSAL OR REPRESSURING WELL BEING USED TO DISPOSE OF WATER FROM THIS LEASE

WELL PLAT

	25		

Amount of surface pipe set and cemented 330' DV Tool Used?

TYPE OF COMPLETION THIS AFFIDAVIT APPLIES TO: (Circle ONE) - Oil, Shut-in Gas, Gas, Dry Disposal, Injection, Temporarily Abandoned. If OWWO, indicate type of re-completion. Other completion. NGPA filing.

ALL REQUIREMENTS OF THE STATUTES, RULES AND REGULATIONS PROMULGATED TO REGULATE THE OIL AND GAS INDUSTRY HAVE BEEN FULLY COMPLIED WITH.

A F F I D A V I T

William H. Bayliff, being of lawful age, hereby certifies that:

I am the Affiant, and I am familiar with the contents of the foregoing Affidavit. The statements and allegations contained therein are true and correct.

Side TWO

OPERATOR IREX Corporation

LEASE NAME Law

SEC 25 TWP 21S RGE 23 (W)

WELL NO 1

FILL IN WELL INFORMATION AS REQUIRED:

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

Show Geological markers, logs run, or other Descriptive information.

Formation description, contents, etc.	Top	Bottom	Name	Depth
---------------------------------------	-----	--------	------	-------

<p>Check if no Drill Stem Tests Run.</p> <p>Check if samples sent Geological Survey.</p>			CDL/CNL	4651'
			Dual latero	4651'
Lime, shale & shell	0'	333'		
Shale	333'	663'		
Red bed	663'	890'		
Anyhrite	890'	950'		
Sand, shale, shell & lime	950'	1820'		
Shale & lime	1820'	2115'		
Lime & shale	2115'	4541'		
Mississippian	4541'	4650'		
Rotary total depth	4650'			
<p>DST #1 4523'-4541', Mississippi Times: 30-45-30-45 minx. Press: IH 2434, FH 2419, IF 24, FIF 34, ISI 106, SIF 34, SFF 38, SSI 106. REC: 63' SOSM IF = wk open blo FF = no open blo - dead.</p>				
<p>DST #2 misrun</p>				
<p>DST #3 4525'-4560', Mississippi Times: 30-45-45-90 mins Press: IH 2406, FH 2406, IF 59, FIF 78, ISI 760, SIF 78, SFF 78, SSI 857. REC: 108'DM</p>				
<p>1st open - very wk 2nd - no blo. If additional space is needed use Page 2</p>				

MAR 26 1984

State Geological Survey
WICHITA BRANCH

Report of all strings set — surface, intermediate, production, etc. CASING RECORD (New) or (Used)

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
SURFACE	12-1/4"	8-5/8"	24#	330'	Common	225	3% cc, 2% gel

LINER RECORD			PERFORATION RECORD		
Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD		
Size	Setting depth	Pecker set at