

7-21-24W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- KEWANEE OIL CO.
Farm- Dave No. 1

SEC. 7 T. 21 R. 24W
NW SW NE
1650' FNL, 2310' FEL

Total Depth. 4427'
Comm. 6-29-59 Comp. 7-26-59
Shot or Treated.
Contractor. Graham-Michaelis Drlg. & K & A Drlg.
Issued. 10-24-59

County Hodgeman
KANSAS



CASING:

8 5/8" 113.50' cem w/150 sx.
5 1/2" 4355.56' cem w/100 sx.

Elevation. 2283' CM

Production. Dry

Figures indicate Bottom of Formations.

surface	0
red bed & shale	990
red bed & shells	1050
sand	1215
red bed & shells	1852
shale & lime shells	2190
shale & lime	2762
lime	2858
lime & shale	4028
lime	4367 RTD
dolomite, chert, shale	4427 CTTD
Total Depth	

TOPS: SAMPLE: C.M. MEAS.
Heebner 3702
Toronto 3720
Douglas 3740
Lansing-Kansas City 3748
Base Kansas City 4108
Cherokee 4268
Conglomerate 4346
Mississippi 4356

TOPS: SCHLUMBERGER C.M. MEAS.
Heebner 3702
Toronto 3720
Douglas 3740
Lansing-Kansas City 3749
Base Kansas City 4108
Cherokee 4267
Basal Penn. Congl. 4346
Mississippi 4353

Treating Record:

7-20-59 Acidized w/1000 gals. 15% regular.
7-23-59 Acidized w/1000 gals. MCA.
7-27-59 Acidized w/500 gals. MCA.

Perforating Record:

open hole - 4355.56' to 4427'.