


7- 21- 24 W

WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY
508 East Murdock, Wichita, Kansas

Company- KEWANEE OIL CO.
Farm- Herman No. 1

SEC. 7 T. 21 R. 24W
SE SE NW
990' fr NL, 330' fr EL
of NW/4
County Hodgeman
KANSAS

Total Depth. 4473' PB 4437'
Comm. 11-7-58 Comp. 11-26-58
Shot or Treated.
Contractor. Graham-Michaelis
Issued. 2-14-59



CASING:
8 5/8" 534.36' cem w/350 sx.
5 1/2" 4468.60' cem w/100 sx.
2 3/8" O.D. Tubing 4431.50'

Elevation. 2288' CM

Production. Swabbed 83.40 BO &
5.13 BW in 11 hrs.

Figures Indicate Bottom of Formations.

surface	0
sand	106
shale	610
sand & red bed	630
red bed	900
Anhydrite, red bed,	
shale & sand	1250
shale	1500
shale & shells	1550
shale & lime	2960
lime	3165
lime & shale	3270
lime	4349
cherty conglomerate	4439
lime	4473 RTD
Total Depth	
Plugged back to 4437'	

TOPS: C.M. MEAS.	SAMPLE	SCHLUMBERGER
Heebner	3704	3706
Toronto	3725	3726
Douglas	3745	--
Lansing-Kansas City	3755	3754
Base Kansas City	4111	4112
Marmaton	4136	4136
Cherokee	4270	4275
Penn. Basal Conglomerate	4353	4354
Mississippi	4368	4368

Treating Record: Acidized w/250 gal. mud
acid by Dowell.

Perforating Record: Perforated 4391' to
4396' (36 - 1/2" holes, (4394-4396 w/9
1/2" bullets per foot and 4391-4394' w/
6-1/2" bullets per foot.)