

20-21-24 W


WELL LOG BUREAU—KANSAS GEOLOGICAL SOCIETY  
508 East Murdock, Wichita, Kansas

Company- PETROLEUM, INC.  
Farm- Adams "F" No. 1

SEC. 20 T. 21 R. 24W  
C NW SE

Total Depth. 4540'  
Comm. 5-15-64 Comp. 6-1-64  
Shot or Treated.  
Contractor. Garvey Drilling  
Issued. 12-19-64

County Hodgeman  
KANSAS



Elevation. 2336' DF

Production. DRY

CASING:

8 5/8" 442' cem w/ 250 sx  
5 1/2" 4537' cem w/ 75 sx

Figures Indicate Bottom of Formations.

shale	460
shale, shells and red bed	945
anhydrite	965
shale & sand	1065
sand	1375
shale, lime & sand	1470
shale	1560
anhydrite # 2	1580
shale & shells	1800
shale	2255
shale & lime	2440
lime	2565
lime & shale	2670
lime	2885
lime & shale	3285
shale & lime	3385
lime & shale	3515
shale & lime w/ chalky stks	3615
lime	3677
lime & chalk	3708
shale & lime	3745
shale, lime & chalk	3855
shale & lime	3919
lime	4392
lime & chert	4430
chert & lime	4440
Mississippi lime	4460
Mississippi lime & chert	4470
chert	4480
Mississippi chert	4500
chert	4540 RTD
Total Depth	

TOPS: SCOUT

Heebner	3778
Lansing	3829
Base Kansas City	4198
Mississippi lime	4426
Mississippi Dolomite	4463
Mississippi Osage	4482