

State Geological Survey KANSAS DRILLERS LOG WICHITA, BRANCH

IMPORTANT
Kans. Geo. Survey request
samples on this well.

API No. 15 — 083 — 20,365
County Number

Operator

O. A. Sutton

Address 800 Sutton Place

Wichita, Kansas 67202

Well No.

#1

Lease Name

Goebel

Footage Location

660

feet from (N) (S) line

660

feet from (E) (W) line

Principal Contractor

Gabbert-Jones, Inc.

Geologist

Richard K. Grant

Spud Date

Spud May 17, 1974

Total Depth

4655'

P.B.T.D.

Date Completed

May 29, 1974


Oil Purchaser

S. 26 T. 21 R. 24 E W

Loc. NW NE

County Hodgeman

640 Acres



Locate well correctly

2425'

Elev.: Gr.

DF 2427' KB 2430'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs./ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface		8-5/8"	24#	537'	common	300	2% gel, 3% cc

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS		Oil bbls.	Gas MCF	Water bbls.	Gas-oil ratio CFPB
Disposition of gas (vented, used on lease or sold)				Producing interval(s)	

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator

O. A. Sutton

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Dry Hole

Well No.

1

Lease Name

Goebel

S 26 T 21 S R 24 E X
W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH

4540'
DST #1, 4508-4540', open 1 hour, rec.
3' mud; IBHP 18# 30 min., FBHP 18#
30 min.; FP 18-18#; temp 127.

DST #2, 4552-4600', open 1 hour, rec.
3' mud; IBHP 30# 30 min., FBHP 10#
30 min.; FP 10-10#; temp 128.

DST #3, 4551-4605', open 1 hour, weak
blow 15 min., died; rec. 3' mud; IBHP
35# 30 min., FBHP 23# 30 min.;
FP 10-10#.

DST #4, 4602-4610', open 1 hour, weak
blow 4 min., died; rec. 5' mud with
few oil specks; IBHP 10# 30 min., FBHP
10# 30 min.; FP 10-10#.

DST #5, 4607-4615', open 1 hour, weak
blow 25 min., died; rec. 70' muddy
water; IBHP 1256# 30 min., FBHP 1244#
30 min.; FP 0-35#.

Log tops:

Heebner

3912 (-1482)

Lansing

3963 (-1533)

Stark shale

4229 (-1799)

BKC

4331 (-1901)

Pawnee

4424 (-1994)

Ft. Scott

4482 (-2052)

Cherokee

4508 (-2078)

Conglomerate

4566 (-2136)


Miss (Warsaw)

4592 (-2162)

Log TD

4655 (-2225)

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

*E. G. McNeil*

Signature

Exploration Manager

Title

October 17, 1974

Date