



KANSAS

PJ

State Geological Survey
WICHITA BRANCH

WELL COMPLETION REPORT AND
DRILLER'S LOG

S. 31 T. 21S R. 24 W
Loc. NW NE Sec. 31-21S-24W
County Hodgeman

API No. 15 — 083 — 20,054-A
County Number

Operator
Phillips Petroleum Company

Address
Box 287, Great Bend, Kansas 67530


Well No. 1 Lease Name
Wright-CB (washdown)

Footage Location
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Slawson Drilling Company Geologist

Spud Date 04-10-81 Date Completed 06-10-81 Total Depth 4580 P.B.T.D. 4580

Directional Deviation Oil and/or Gas Purchaser
Koch



640 Acres
N
Locate well correctly
Elev.: Gr. 2374'
DF 2376 KB 2379

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Secks	Type and percent additives
Surface	12 1/4"	8 5/8"	24#	524'	Common	275 sx	2% cc
Production	7 7/8"	5 1/2"	15.5#	4576.61	60-40 Pozmix	225 sx	10% salt, 3/4% CFR-2 & Halad 9

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Secks cement	Shots per ft.	Size & type	Depth interval
			2 HPF	19 Gm Jet	4493-99, 4484-89'
TUBING RECORD			(Squeezed the above perfs & reperf'd)		
Size	Setting depth	Pecker set at			
2 3/8"	4483'		2 HPF	SSB II 19 Gm Jet	4484-89'

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
750 gal MSR Acid	4493-99, 4484-89
Squeezed Perfs w/50 sx Class A Common Cement	4493-99, 4484-89
500 gal RA-8, 250 gal XXW-39	4484-89

INITIAL PRODUCTION

Date of first production <u>06-10-81</u>	Producing method (flowing, pumping, gas lift, etc.) <u>Pumping</u>
RATE OF PRODUCTION PER 24 HOURS	Oil <u>11</u> bbls. Gas <u>--</u> MCF Water <u>19</u> bbls. Gas-oil ratio <u>--</u> CFPB
Disposition of gas (vented, used on lease or sold) <u>-----</u>	Producing interval(s) <u>4484'-89'</u>

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Phillips Petroleum Company DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:

Well No. 1 Lease Name Wright-CB OIL

S 31 T 21 S R 24 ~~25~~ W Hodgeman County, Kansas

WELL LOG
 Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries. SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface	0		Log Tops:	
(Washdown)			Heebner	3817'
			LKC	3869'
			Marmaton	4265'
			Fort Scott	4392'
			Miss	4480'
RTD		4580'		

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received _____
 Signature C. D. Doherty
 District Superintendent
 Title
 Date 06-12-81

31-21-24W

DRILLER'S LOG A

COMPANY
CONTRACTOR
FARM
LOCATION

COMMENCED
COMPLETED

Phillips Petroleum Co.
~~Phillips Petroleum Company~~
LEBEN DRILLING, INC.
WRIGHT B-1
C NW NE SECTION 31-21S-24W
HODGEMAN COUNTY, KANSAS
9-28-68
10-9-68

0 524
524 675
675 1596
1596 1630
1630 1820
1820 2305
2305 2567
2567 2610
2610 2820
2820 3480
3480 3800
3800 4075
4075 4580
4580

MAR 03 1986
State Geological Survey
WICHITA BRANCH

Shale, Sand
Shale, Shells
Redbed, Sand
Anhydrite
Shale, Shells
Shale
Shale, Lime Streaks
Lime
Shale, Lime
Lime, Shale
Shale
Lime, Shale
Lime
RTD - D. & A.

Washed down by Phillips Petroleum Co. 4-10-81

8 5/8" 24# used surface casing set @ 524' cemented with 75 sacks
Common cement, 17 cc

I, Leslie Kite, do hereby certify that the above and foregoing is
a true and correct copy of the log of the Wright B-1 Well, located
C NW NE of Section 31, Township 21 South, Range 24 West, Hodgeman
County, Kansas, as reflected by the records of Leben Drilling, Inc.



Leslie Kite

STATE OF KANSAS)
COUNTY OF BARTON) SS

Subscribed and sworn to and before me, a Notary Public, in
and for Barton County, Kansas, this 14th day of October, 1968.



WPS-15-1E

Small, faint, illegible text or markings.