

KANSAS DRILLERS LOG

State Geological Survey
WICHITA, BRANCH

API No. 15 — 033 — 20,393
County Number

Operator

Petroleum, Inc.

Address

300 West Douglas Wichita, Kansas 67202

Well No.

#1

Lease Name

Dykes "B"

Footage Location

660

feet from (N) XX line

510

feet from (E) XX line

NE/4

Principal Contractor

DNB Drilling

Geologist

Deane Jirrels

Spud Date

9-8-74

Total Depth

RTD 4618

P.B.T.D.

Date Completed

9-16 -1974


Oil Purchaser

S. 32 T. 21 R. 24 E W

Loc. A/C NE NE

County Hodgeman

640 Acres



Locate well correctly

Elev.: Gr. 2408'

DF 2410' KB 2413'

CASING RECORD

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
surface		8-5/8"		558'	Common	250	4% gel, 3% c.c.
					Common	150	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

Size	Setting depth	Packer set at			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated

INITIAL PRODUCTION

Date of first production		Producing method (flowing, pumping, gas lift, etc.)			
RATE OF PRODUCTION PER 24 HOURS	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval (s)		

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

rator

Petroleum, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Dry Hole

Well No.

#1

Lease Name

DYKES 'B'

S 32 T 21S R 24 W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.

TOP

BOTTOM

NAME

DEPTH


DST #1: 4536'-4578'; 30''-30''-60''-60'';
wk blow. Rec. 70' VSOCM;
IFP 35#-47#, FFP 53#-59#,
BHP 82#-71#, T-127°.

DST #2: 4578'-4593': 30''-30''-30''-30'';
wk blow 30''. Rec. 15' M/f spks
oil; IFP 0#, FFP 0#, BHP 23#-
23#, T-127°.

DST #3: 4593'-4618'; 30''-30''-30''-30'';
wk blow 30''. Rec. 10' Mud,
IFP 0#, FFP 0#, BHP 1136#-1055#,
T-127°.

T/Anh 1646
B/Anh 1680
Heebner 3886
Lsg 3944
Hertha 4254
Marm 4347
Ft. S 4462
Miss 4562

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



Jay C. McNeil

Signature

District Geologist

Title

9-25-74

Date

DRILLERS' LOG

32-21-24W

PETROLEUM, INC.
No. 1 Dykes
C NE NE, Sec. 32-21S-24W
Hodgeman County, Kansas

15-083-20,393

Elevation: 2413 K.B.

Commenced: 9-8-73
Completed: 9-16-74

Surface Casing: 558' of
8-5/8" cemented w/250 sx
common cement, 4% Gel,
3% cc.

<u>FORMATION</u>	<u>DEPTH</u>
Surface Hole	0 - 566
Shale	566 - 1045
Blaine Anhydrite	1045 - 1053
Shale & Sand	1053 - 1320
Shale & Red Bed	1320 - 1530
Red Bed	1530 - 1646
Anhydrite	1646 - 1681
Shale	1681 - 2075
Shale & Lime	2075 - 2510
Lime & Shale	2510 - 3105
Shale & Lime	3105 - 3705
Lime & Shale	3705 - 3965
Lime	3965 - 4618 T.D.

I do hereby certify that the foregoing statements are true and correct to the best of my knowledge and belief.

D N B DRILLING, INC.

James L. Donelson
JAMES L. DONELSON



STATE OF KANSAS: ss:

Subscribed and sworn to before me, the undersigned, a Notary Public in and for said state, this 18th day of September, 1974.

My Commission Expires:
August 25, 1976

Ella Priess
Ella Priess, Notary Public

