


Wichita, Kansas

OCT 13 1972

33-2-24W
CSE NE



GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

API # 15-083-20, 227

151 Bopn

2399 KB

✓

L

RINDLEY #1
C SE NE
Section 33-21S-24W
Hodgeman County, Kansas

Commenced: May 15, 1972
Completed: June 2, 1972

OPERATOR: OASIS PETROLEUM, INC.

| Depth | | Formation | Remarks |
|-------|------|--------------|---|
| From | To | | |
| 0 | 554 | Shale-sand | Ran 12 double joints and 1 single joint of used 28# 8 5/8" csg. set @ 551' cemented w/300 sks common w/2% Gel - 3% CC Cement Cir. P.D. @ 5:30 AM 5/16/72 |
| 554 | 1010 | Shale-shells | |
| 1010 | 1615 | Shale-sand | |
| 1615 | 1658 | Shale-redbed | |
| 1658 | 1696 | Anhydrite | |
| 1696 | 1900 | Shale-redbed | |
| 1900 | 2547 | Shale | |
| 2547 | 3890 | Lime-shale | |
| 3890 | 3950 | Lime | |
| 3950 | 4200 | Lime-shale | |
| 4200 | 4560 | Lime | Ran 147 joints of used 15# 5 1/2" csg. set @ 4684' cemented w/150 sks salt sat. D.V. Tool @ 3034' cemented w/375 sks Halcolite. Job Complete @ 12:45 PM 6/2/72 |
| 4560 | 4594 | Lime-chert | |
| 4594 | 4685 | Lime | |
| 4685 | TD | | |

LOG TOPS
ANHY 1647
HEEB 3896
LANS 3945
BKC 4325
FT SC 4474
CONG 4545
MISS DOL 4580
MISS OS 4647
RTD 4685

II, certify this is a correct copy of the Drillers' he C SE NE, Section 33-21S-24W, Hodgeman County, wedge and belief.

James S. Sutton, II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 6th day of June, 1972, personally appeared James S. Sutton, II, to me personally known to be the identical person who executed the within and foregoing instrument and acknowledged to me that he executed the same as his free and voluntary act and deed for the uses and purposes therein set forth.

IN WITNESS WHEREOF, I have hereunto set my hand and official seal the day and year last above written.