


KANSAS GEOLOGICAL SOCIETY
508 East Murdock
Wichita, Kansas

OCT 13 1972

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

33-21-24W
CSWNE



API # 15-083-20,228

131 BOPD

2435 KB

L
V

BINDLEY #2
C SW NE, Section 33-21S-24W
Hodgeman County, Kansas


Commenced: June 17, 1972
Completed: June 29, 1972

OPERATOR: OASIS PETROLEUM, INC.

Depth From	To	Formation	Remarks
0	65	Surface clay-sand	Ran 13 double joints of used 8 5/8"
65	350	Shale	csg. set @ 558' cemented w/300 sks
350	475	Sand	common 3% CC 2% Gel
475	1042	Shale	P.D. @ 12:30 AM 6/18/72
1042	1095	Blaine Anhydrite	Cement Circ.
1095	1160	Shale	
1160	1350	Sand	
1350	1715	Shale-sand	LOG TOPS
1715	2054	Shale	ANHY 1684
2054	2300	Shale-lime	HEEB 3933
2300	2500	Lime-shale	LANS 3982
2500	2650	Lime	STARK 4253
2650	2785	Lime-shale	BKC 4365
2785	2925	Lime	FT SC 4515
2925	3795	Shale-lime	CONG 4592
3795	4295	Lime	MISS DOL 4622
4295	4380	Lime-shale	MISS OS 4694
4380	4636	Lime	TD 4731
4636	4649	Core #1	
4649	4689	Core #2	
4689	4730	Lime	
4730	TD		

Ran 150 joints of used #14 5 1/2" csg.
set @ 4729' cemented w/150 sks common
2% Gel, 100 sks salt sat Posmix
DV Tool @1684 cemented w/350 sks
common.
P.D. @ 3:25 AM
Job Completed 4:35 AM
6/29/1972

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the C SW NE, Section 33-21S-24W, Hodgeman County, Kansas, to the best of my knowledge and belief.


James S. Sutton, II

STATE OF KANSAS)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned...