

KANSAS DRILLERS LOG

State Geological Survey

API No. 15 — 083 — 20331
County Number

Operator

Oasis Petroleum, Inc.

Address

3535 N.W. 58th Street, Oklahoma City, Oklahoma 73112

Well No. 4 Lease Name Bindley

Footage Location

730 feet from (N) ~~SD~~ line 1980 feet from (E) ~~(SW)~~ line

Principal Contractor Gabbert-Jones Drilg. Co. Geologist Charles O. Tucker


Spud Date 9-26-73 Total Depth 4710' P.B.T.D. 4665'

Date Completed 11-27-73 Oil Purchaser Koch Oil Company

S. 33 T. 21 R. 24 ^E
_W

Loc. NW NE

County Hodgeman

640 Acres
N

Locate well correctly

2417'

Elev.: Gr.

DF _____ KB 2422'

CASING RECORD

Report of all strings set—surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4	8 5/8	24	561	Class H	375	gel & Ca.CI.
Production	7 7/8	5 1/2	14	4704	Halcolite	150	
					Common	150	salt & CFR 2
			DV tool at 1696'		Howcolite	325	

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

TUBING RECORD

2 jets 4610-19 & 4630-4

Size	Setting depth	Packer set at
2 7/8"	4659'	-----

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
5,000 gals 15% MOD-202 acid	4610-40'

INITIAL PRODUCTION

Date of first production	Producing method (flowing, pumping, slug, etc.)
11-27-73	Pumping

RATE OF PRODUCTION PER 24 HOURS	Oil 150 bbls.	Gas 0 MCF	Gas-oil ratio ----- CFPB

Disposition of gas (vented, used on lease or sold)	Producing interval	Mississippi
		4610-19' & 4630-40'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

RECEIVED
STATE CORPORATION COMMISSION
JAN 21 1974
CONSERVATION DIVISION
WICHITA, KAN.

Operator

Oasis Petroleum, Inc.

DESIGNATE TYPE OF COMP.: OIL, GAS,
DRY HOLE, SWDW, ETC.:

Well No.

4

Lease Name
Bindley

oil

S 33 T 21 R 24 ~~Z~~ W

WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN,
OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Mississippi	4607			
See attached driller's log.				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received

David C. Holk

Signature

Production Engineer

Title

1-4-74

Date _____

33- 21- 24W

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

BINDLEY #4
C NW NE, Sec. 33-21S-24W
Hodgeman County, Kansas

COMMENCED: October 26, 1973
COMPLETED: November 5, 1973

OPERATOR: -Oasis Petroleum, Inc.

From	To	Depth	Formation	Remarks
0	75	75	Surface Clay-Sand	Ran 14 jts. of New 23#
75	380	380	Shale	8 5/8" casing set @561'
380	455	455	Sand-Shale	cemented w/225 sks. com-
455	568	568	Shale	mon cement, 3% CC, 2% Gel,
568	865	865	Redbed-Shale	150 sks. common cement,
865	1148	1148	Shale w/Anhydrite Streaks	3% CC. Cement circ.
1148	1346	1346	Sand	P.D. @7:00 PM 10-26-73
1346	1674	1674	Shale	
1674	1716	1716	Anhydrite	
1716	1870	1870	Shale	
1870	2510	2510	Shale-Lime	
2510	2800	2800	Lime	
2800	3095	3095	Lime-Shale	
3095	3669	3669	Shale-Lime	
3669	3725	3725	Sandy Lime-Shale	
3725	3925	3925	Lime-Shale	
3925	4145	4145	Lime	
4145	4285	4285	Lime-Shale Streaks	
4285	4710	4710	Lime	

4710 Total Depth

I, James S. Sutton II, certify this is a correct copy of the Drillers' Log for the well drilled in the C NW NE of Sec. 33-21S-24W, Hodgeman County, Kansas to the best of my knowledge and belief.



JAMES S. SUTTON II

STATE OF KANSAS)
)
) SS
COUNTY OF SEDGWICK)

Before me, the undersigned, a Notary Public within and for said County and State, on this 13th day of November, 1973, personally appeared James S. Sutton II to me personally known to be the identical person who executed the within and fore-