

KANSAS

**WELL COMPLETION REPORT AND
DRILLER'S LOG**

State Geological Survey R. 24 W
WICHITA BRANCH 20' ENL & 1320' FEL

API No. 15 — 083 — 20,784
County Number

Operator
Conoco Inc.

Address
3535 N.W. 58th St. Oklahoma City, Okla. 73112

Well No. 5 Lease Name Bindley

Footage Location
1320 feet from (N) (S) line and 1320 feet from (E) (W) line

Principal Contractor Slawson Drilling Co. Geologist L. O. Chubb

Spud Date 11-15-80 Date Completed 12-23-80 Total Depth 4,700' P.B.T.D. 4,668'

Directional Deviation 1 1/4° @ TD Oil and/or Gas Purchaser Koch Oil Company

County Hodgeman
640 Acres
N
160 160 160 160
33
Locate well correctly
Elev.: Gr. 2417'
DF KB 2422'

CASING RECORD

Report of all strings set— surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	10 3/4"	8 5/8"	24#	717'	Class A	375	2% Gel 3% CaCl ₂
Production	7 1/4"	5 1/2"	14#	4699'	Class A	650	10% Salt 1% CFR -2

LINER RECORD

PERFORATION RECORD

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval
TUBING RECORD			2 JSPF	Golden Jet	4616-4626
Size 2 7/8"	Setting depth 4660'	Packer set at None			

ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD

Amount and kind of material used	Depth interval treated
Acidized w/200 gal. Halco Soap, 1050 gal. Mod. 202, max press 150 PSI, 1 1/2 BPM.	4616'-4626'

INITIAL PRODUCTION

Date of first production 12-23-80 Producing method (flowing, pumping, gas lift, etc.) Pumping

RATE OF PRODUCTION PER 24 HOURS
Oil 30 bbls. Gas 0 MCF Water 2 bbls. Gas-oil ratio CFPB

Disposition of gas (vented, used on lease or sold) None Producing interval(s) Mississippi 4609' to 4670'

INSTRUCTIONS: As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 245 No. Water, Wichita, Kansas 67202. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Conoco Inc.		DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.:
Well No. 5	Lease Name Bindley	Oil Well
S 33 T 21 R 24 W		


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Heeber Shale	3,922			
Lansing	3,972			
Stark Shale	4,238			
Base Kansas City	4,353			
Pawnee	4,460			
Cherokee	4,526			
T/Mississippi	4,613			

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.

Date Received	 Larry E. Jenkins Signature
	Administrative Supervisor Title
	January 5, 1981 Date

PT

33-21-24W

DRILLERS LOG

State Geological Survey
WICHITA BRANCH

OPERATOR: CONOCO, Inc.
3535 NW 58th
National Found.Life Building
Oklahoma City, Oklahoma 73112

WELL NAME: Oasis-Bindley #5
Sec.33-21S-24W
Hodgeman County, Kansas

CONTRACTOR: Slawson Drilling Company, Inc.
200 Douglas Building
Wichita, Kansas 67202

COMMENCED: 11/15/80

COMPLETED: 11/23/80

RTD: 4700'

SURFACE CASING: 8-5/8" set at 727' with 375 sx cement

PRODUCTION CASING: 5-1/2" set at 4699' with 650 sx cement

0' to 730' Surface Hole
730' to 3510' Shale
3510' to 4070' Shale & Lime
4070' to 4375' Lime
4375' to 4485' Shale & Lime
4485' to 4700' Lime
RTD 4700'

STATE OF KANSAS
COUNTY OF SEDGWICK

I, James C. Remsberg, of the Slawson Drilling Company, Inc.
hereby state the above is an accurate copy of the Oasis-Bindley #5
log for CONOCO, Inc.

James C. Remsberg
James C. Remsberg

Subscribed and sworn to
me this 11th day of December, 1980

Mary Lou Taylor
Mary Lou Taylor, Notary