

State Geological Survey  
WICHITA, BRANCH

**KANSAS DRILLERS LOG**

S. 33 T. 21 R. 24W <sup>E</sup>/<sub>W</sub>

API No. 15 — 083 — 20421  
County Number

Loc. C NW NW

County Hodgeman

Operator  
Donald C. Slawson

Address  
408 120 Building, Wichita, Kansas 67202


Well No. #1 Lease Name Sorem 'A'

Footage Location  
feet from (N) (S) line feet from (E) (W) line

Principal Contractor Slawson Drilling Company, Inc. Geologist Bob Jenkins

Spud Date March 18, 1975 Total Depth 4646 P.B.T.D.

Date Completed March 27, 1975 Oil Purchaser N/A



Elev.: Gr. 2433

DF 2435 KB 2438

**CASING RECORD**

Report of all strings set — surface, intermediate, production, etc.

Purpose of string	Size hole drilled	Size casing set (in O.D.)	Weight lbs/ft.	Setting depth	Type cement	Sacks	Type and percent additives
Surface	12 1/4"	8 5/8"		569'	60/40 Poz	400 sx	

**LINER RECORD**

**PERFORATION RECORD**

Top, ft.	Bottom, ft.	Sacks cement	Shots per ft.	Size & type	Depth interval

**TUBING RECORD**

Size	Setting depth	Pecker set at

**ACID, FRACTURE, SHOT, CEMENT SQUEEZE RECORD**

Amount and kind of material used	Depth interval treated

**INITIAL PRODUCTION**

Date of first production	Producing method (flowing, pumping, gas lift, etc.)				
<b>RATE OF PRODUCTION PER 24 HOURS</b>	Oil	Gas	Water	Gas-oil ratio	
	bbls.	MCF	bbls.	CFPB	
Disposition of gas (vented, used on lease or sold)			Producing interval(s)		

**INSTRUCTIONS:** As provided in KCC Rule 82-2-125, within 90 days after completion of a well, one completed copy of this Drillers Log shall be transmitted to the State Geological Survey of Kansas, 4150 Monroe Street, Wichita, Kansas 67209. Copies of this form are available from the Conservation Division, State Corporation Commission, 3830 So. Meridian (P.O. Box 17027), Wichita, Kansas 66217. Phone AC 316-522-2206. If confidential custody is desired, please note Rule 82-2-125. Drillers Logs will be on open file in the Oil and Gas Division, State Geological Survey of Kansas, Lawrence, Kansas 66044.

Operator Donald C. Slawson

DESIGNATE TYPE OF COMP.: OIL, GAS, DRY HOLE, SWDW, ETC.: Dry Hole

Well No. #1

Lease Name Sorem 'A'

S 33 T 21 R 24W E W


WELL LOG

Show all important zones of porosity and contents thereof; cored intervals, and all drill-stem tests, including depth interval tested, cushion used, time tool open, flowing and shut-in pressures, and recoveries.

SHOW GEOLOGICAL MARKERS, LOGS RUN, OR OTHER DESCRIPTIVE INFORMATION.

FORMATION DESCRIPTION, CONTENTS, ETC.	TOP	BOTTOM	NAME	DEPTH
Surface hole	0	498	No E Log	
Shale and Sand	498	583		
Shale and Shells	583	1623		
Shale	1623	1678		
Anhydrite	1678	1715		
Shale	1715	2500		
Shale and Lime	2500	3630		
Lime	3630	3788		
Lime and Shale	3788	4529		
Lime	4529	4628		
Lime and Shale	4628	4646		
RTD		4646		
DST #1 4519-4628, 30-45-45-60, WBTC Rec. 210' TF, 150' M, 60' SOCM w/spks 0, IFP 18-64#, FFP 73-100#, IBHP 1007#, FBHP 980#				
DST #2 4628-4646, 30-45-45-60, WBTC Rec. 80' wtry M (75% M, 25% W) IFP 27-32, ISIP 1135#, FFP 36-45#, FSIP 1089#				

USE ADDITIONAL SHEETS, IF NECESSARY, TO COMPLETE WELL RECORD.



*James C. Remsberg*  
 James C. Remsberg, Petroleum Engineer  
 Title  
 April 4, 1975  
 Date

