


34-21-24W
C SE SE34-21-24W
KANSAS

GABBERT-JONES, INC.
WICHITA, KANSAS
DRILLERS' WELL LOG

API# 15-083-20,277

LOG TOPS:

EVERTON #2
C SW SE, Sec. 34-21S-24W (C SE SE - Intent)
Hodgeman County, Kansas

Commenced: December 11, 1972
Completed: December 22, 1972

OPERATOR: OASIS PETROLEUM, INC.

80VI	YHWA
438E	HEEB
010A	LKC
18SA	STARK
SA2A	FT SC
SA2A	MISS
80TA	LTD
20TA	RTD

Depth		Formation	Remarks
From	To		
0	60	Surface clay-sand	Ran 14 joints of used 28# double joints 8 5/8" csg set @ 605' cemented w/150 sks Howcolite 2% CC - 125 Sks common 3% CC, 2% Gel. P.D. @ 12:00 AM 12/11/1972 Cement Circ.
60	217	Shale	
217	612	Shale-sand	
612	1040	Redbed-shale	
1040	1180	Shale w/lime stks	
1180	1385	Sand	
1385	1705	Shale-shells	
1705	1715	Shale	
1715	1755	Anhydrite	
1755	2385	Shale-lime	
2385	2495	Lime-shale	LOG TOPS: ANHY 1708 HEEB 3964 LKC 4010 STARK 4281 FT SC 4542 MISS 4642 LTD 4703 RTD 4705 Ran 148 joints of 14 and 15# 5 1/2" csg. set @ 4704' cemented w/175 sks Howcolite - 100 Sks Salt Sat 50-50 Posnix. 20 Bbl salt flush ahead of cement. D.V. Tool @ 1729' cemented w/300 sks Howcolite Job completed @ 7:45 AM 12/22/1972
2495	2510	Shale-lime	
2510	2590	Lime-shale	
2590	2927	Lime	
2927	3100	Lime-shale	
3100	3460	Shale-lime	
3460	4210	Lime-shale	
4210	4642	Lime	
4642	4701	Coring	
4701	4705	Lime	
4705	TD		

I, James S. Sutton, II, certify this is a correct copy of the Drillers' Log for the well drilled in the C SW SE, Section 34-21S-24W, Hodgeman County, Kansas, to the best of my knowledge and belief.

James S. Sutton, II
James S. Sutton, II